

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-051-04336-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Ellis County, Sec. 30 Twp. 12S Rge. 17W (E) (W)

Location as "NE/CNWxSWx" or footage from lines Approx C E 1/2 SE SE

Lease Owner ALPINE OIL & ROYALTY CO., INC.

Lease Name KARLIN Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed October 19, 1959 19

Application for plugging filed October 19, 1959 19

Application for plugging approved October 19, 1959 19

Plugging commenced October 19, 1959 19

Plugging completed October 19, 1959 19

Reason for abandonment of well or producing formation non-productive in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3675 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	160	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud from total depth - 3675 - to 540 feet.  
Solid plug at 540 feet with 20 sacks cement  
Another plug at 150 feet with 15 sacks cement  
Cement to 40 feet - another plug and 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
10-27-1959  
OCT 27 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.  
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) *Thomas M. McCaul*  
800 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 19 59  
*Virginia Marshall*  
Notary Public.  
My commission expires August 10, 1961

15-051-04336-00-00

P  
WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: October 10, 1959

Contractor: Quaker Drilling Co., Inc.

Completed: October 19, 1959

Karlin No. 1  
Approx. C E $\frac{1}{2}$  SE SE  
Section 30-12<sup>S</sup>-17W  
Ellis County, Kansas

Elevation: 2092 K. B.

Production: D. & A.

Casing Record

Set 8 5/8" casing at 160 feet with 150 sacks cement

(The Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Shale	320	Heebner	3321 -1229
Shale and Shells	790	Toronto	3343 -1251
Sand	980	Lansing	3367 -1275
Red Bed	1314	Base of Kansas City	3594 -1502
Anhydrite	1354	Conglomerate	3603 -1511
Shale and Shells	1660	Rotary Total Depth	3675 -1583
Lime and Shale	1900		
Lime	2015		
Lime and Shale	3365		
Lime	3594		
Shale and Lime	3675		

RECEIVED  
STATE CORPORATION COMMISSION  
10-27-1959  
OCT 27 1959

CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the approximate Center of the E $\frac{1}{2}$  SE $\frac{1}{4}$  SE $\frac{1}{4}$  of Section 30, Township 12 South, Range 17 West, Ellis County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul  
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me a Notary Public this 23rd day of October, 1959.

Virginia Mandell  
Virginia Mandell, Notary Public

MY COMMISSION EXPIRES:  
August 10, 1961