

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

15-051-23719-00-00  
WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_

LEASE NAME Staab #3

WELL NUMBER \_\_\_\_\_

SPOT LOCATION NW SE SW

SEC. 31 TWP. 12 SRGE. 17 W (E) or (W)

COUNTY Ellis

Date Well Completed \_\_\_\_\_

Plugging Commenced 9/3/85

Plugging Completed 9/11/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Francis V. Weigel

ADDRESS Box 244, Gorham, Ks. 67640

PHONE # (913) 637-5383 OPERATORS LICENSE NO. 6772

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3688'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	248'	none
				5 1/2"	3687'	2750'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3375' & 5 sacks cement. Shot pipe at 3010', 2918', 2815', & 2750'. Pulled 68 joints of pipe. Plugged well with 4 hulls, 35 cement, 12 gel, 70 cement, 3 gel, 1 hull, plug & 100 sacks 50/50 poz 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

RECEIVED  
STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

9-27-85  
SEP 27 1985

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 26 day of September, 19 85

My Commission expires:



Irene Hoover  
Notary Public