



KANSAS CORPORATION COMMISSION 1032573  
OIL & GAS CONSERVATION DIVISION

Form CP-1  
March 2009

This Form must be Typed  
Form must be Signed  
All blanks must be Filled

**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

OPERATOR: License #: 30535  
Name: Hartman Oil Co., Inc.  
Address 1: 10500 E. BERKELEY SQ PKWY STE 100  
Address 2: \_\_\_\_\_  
City: WICHITA State: KS Zip: 67206 + \_\_\_\_\_  
Contact Person: Stan Mitchell  
Phone: (620) 636-2090

API No. ~~15~~ - 15-055-20172-00-00  
If pre 1967, supply original completion date: n/a  
Spot Description: \_\_\_\_\_  
NW SE SE Sec. 33 Twp. 22 S. R. 33  East  West  
660 Feet from  North /  South Line of Section  
660 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Finney  
Lease Name: DAMME Well #: 18

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8.625 Set at: 350 Cemented with: 255 Sacks  
Production Casing Size: 5.5 Set at: 4550 Cemented with: 150 Sacks

List (ALL) Perforations and Bridge Plug Sets:  
**Attached**

Elevation: 2882 ( G.L. /  K.B.) T.D.: 4550 P.B.T.D.: 4540 Anhydrite Depth: 1850  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: -  
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):  
SET 1ST CIBP @ 4360' CAP W/ 2 SKS CEMENT - SET 2ND CIBP @ 1100' CAP W/ 2 SKS CEMENT - TEST CSG TO 500# - PERFORATE 2 HOLES @ 1075'  
CIRCULATE DOWN 5-1/2" CSG W/ 300 SKS 60-40 POZ W/ 4% GEL CEMENT TO SURFACE - IF CEMENT DOES NOT CIRCULATE ~~PERFORATE~~ SKS DOWN  
8-5/8" SURFACE - OR AS PER KCC  
**RECEIVED**  
**KANSAS CORPORATION COMMISSION**

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No  
If ACO-1 not filed, explain why: \_\_\_\_\_

**30**  
**OCT 03 2009** *PRT*

**CONSERVATION DIVISION**  
**WICHITA, KS**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission  
Company Representative authorized to supervise plugging operations: STAN MITCHELL  
Address: 3545 W. JONES Ave. City: GARDEN CITY State: KS Zip: 67846 + \_\_\_\_\_  
Phone: (620) 277-2511  
Plugging Contractor License #: 33645 Name: H2 Plains, LLC  
Address 1: PO BOX 346 Address 2: \_\_\_\_\_  
City: NESS CITY State: KS Zip: 67560 + 0346  
Phone: (785) 798-3995  
Proposed Date of Plugging (if known): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

**Submitted Electronically**

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*DG*

Form	CP1 - Well Plugging Application
Operator	Hartman Oil Co., Inc.
Well Name	DAMME 18
Doc ID	1032573

Perforations And Bridge Plug Sets

Perforation Top	Perforation Base	Formation	Bridge Plug Depth
4387	4391	Marmanton	



Mark Parkinson, Governor  
Thomas E. Wright, Chairman  
Michael C. Moffet, Commissioner  
Joseph F. Harkins, Commissioner

October 30, 2009

Stan Mitchell  
Hartman Oil Co., Inc.  
10500 E BERKELEY SQ PKWY STE 100  
WICHITA, KS 67206

Re: Plugging Application  
API 15-055-20172-00-00  
DAMME 18  
SE/4 Sec.33-22S-33W  
Finney County, Kansas

Dear Stan Mitchell:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after April 28, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,  
Production Department Supervisor

cc: District 1

(620) 225-8888