



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-051-22988-00-00

Dear Sir:

Mr. Bruce Fickel of Emphasis Oil Operations has this
date requested permission to plug the following described well:

Operator's Full Name: N-B Company

Complete Address: P. O. Box 506, Russell, Kansas 67665

Lease Name: Reitmayer Well No. #3

Location: SE SE NW Sec. 17 Twp. 12 Rge. 20 (E) (W)

County: Ellis Total Depth: 4050'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereafter indicated:

Mr. Bruce Fickel was instructed to plug the well as follows:

8 5/8"-240' s.p. cuc. w/160 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 910' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1982

Very truly yours,

[Signature]
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas