



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

15-051-01240-00-00

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date 7-21-58, 19, authorized the following plugging operation:

Operator's Full Name: Nadel & Gussman

Complete Address: 625 Union Center Wichita, Kans

Lease Name: Reitmeyer Well No. 1

Location: NE NE NW Sec. 17 Twp. 12 Rge. 20 (E) (W)

County: Ellis Total Depth: 4000

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Circulated hole with heavy mud, set plug at 675', displace 20 sax cement through drill pipe, mud to 180', set plug and 20 sax cement through drill pipe, heavy mud to 40', set plug, 1/2 sack hulls and 10 sax cement.

Very truly yours,

Signed: [Signature] Conservation Division Agent

07-29-1958