

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Mike Cherry of Phillips Petroleum ~~State~~ has this

date requested permission to plug the following described well:

Operator's Full Name: Phillips Petroleum Co.

Complete Address: Box 287 St Bend, Mo. 67530

Lease Name: Earl 'e' Well No. 7

Location: NW-SW-NE Sec. 13 Twp. 10 Rge. 20 (E) (W)

County: Boone Total Depth: 3749

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Cherry was instructed to plug the well as follows:

8 5/8" @ 258' w/175 or 5 1/2" @ 3748' w/150 or

Openhole comp. 3746-49- Squeezed @ 997' w/300 or.

cmt. w/1850 # PSI - Squeezed @ 1260' in 1952

Ordered 250oz 50/50 polymer 6% gel 3% CC, 14 gel, 7 hulls +

5 1/2" plug. Pumped in 5 1/2 1-hulls -> 50 cmt. + 2 hulls -> 14

gel + 2 hulls -> 5 1/2 wiper plug -> 85 cmt. + 2 hulls - 400 # PSI

shut in: Hood - up to 8 5/8" pumped 90 or cmt PSI to 500 #

PSI shut in

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1982
09-14-82
CONSERVATION DIVISION
Wichita, Kansas

Dennis L. Hamel
Conservation Division Agent