

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

DRILLED 8/51

API NUMBER 15-163-03295 -0000 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR BP Exploration Inc. OPERATORS LICENSE NO. 6854

ADDRESS P.O. Box 4587 Houston, TX 77210 PHONE # (713) 552-8500

LEASE (FARM) Desbian WELL NO. 5 WELL LOCATION SE-SE-NE COUNTY Rooks

SEC. 12 TWP. 10S RGE. 20 (E) or (W) TOTAL DEPTH 3827' PLUG BACK TD _____

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 346' CEMENTED WITH 200 SACKS

CASING SIZE 5-1/2" SET AT 3774' CEMENTED WITH 150 SACKS

PERFORATED AT Casing 3-1/2" liner 3766-3822'
3780-84' (open); 3536-3628' (squeezed)

CONDITION OF WELL: GOOD _____ POOR CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL

squeeze producing zone with 25+ sx of POZMIX cement, spot 60 sx plug in liner and casing to 3000'. WOC. Spot 130 sx cement plug in casing to 1200'. WOC. perforate casing above second cement plug. Attempt to circulate cement behind 5-1/2" casing to surface and fill 5-1/2" csg with cement to the surface, combine volumes 230 sx POZ mix. Cut csg below plow depth & weld on steel cap.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 10-30-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION. 10-12-89

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Joel Stull PHONE # (913) 637-5290

ADDRESS Gorham, KS 67640

PLUGGING CONTRACTOR Halliburton LICENSE NO. 5287

ADDRESS 1100 East 8th St. Hays, KS 67601 PHONE # (913) 625-5290

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Joanne Husko
(Operator or Agent)

DATE: 10-6-89

(4)



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

JAN 12 1990

EXPIRES

October 12, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

BP Exploration, Inc.
P.O. Box 4587
Houston, TX 77210

Desbian 5
SE SE NE
12-10-20W
Rooks County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #4 2301 E. 13th

Hays, KS 67601

(913) 628-1200
