

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-02071-00-00 (of this well) - Drilled 11/18/49
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR BP EXPLORATION INC. OPERATORS LICENSE NO. 06854 *g/2*

ADDRESS P. O. Box 4587, Houston, Texas 77210 PHONE # (713) 552-8500

LEASE (FARM) EARL SUTOR WELL NO. 1 WELL LOCATION SE-SE COUNTY ROOKS

SEC. 12 TWP. 10S RGE. 20W (E) or (W) TOTAL DEPTH 3776' PLUG BACK TD 3748'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1659' CEMENTED WITH 625 SACKS

CASING SIZE 5-1/2" SET AT 3774' CEMENTED WITH 100 SACKS

PERFORATED AT 3522'-3679' LANSING-KANSAS CITY

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL ¹⁾ Set retainer at 3450', squeeze perforations and spot 100' of Pozmix 65/35 cement on top of retainer, total volume = 50 sx; 2) perforate squeeze holes in 5-1/2" casing at 1700'. Set retainer, circulate cement to surface via 8-5/8"/5-1/2" annulus (volume = sx), spot 100' of cement on top of retainer (volume = 226 sx); 3) spot 100' surface plug, 10 sx Pozmix. Cut casing. Weld on steel plate. NOTE: 9.0 ppg mud (if additional space is needed use back of form)

(36 visc.) will be placed in well between cement plugs.
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO LOGS AVAILABLE IS ACO-1 FILED? ?
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN December 5, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

JOEL STULL PHONE # (913) 637-5290

ADDRESS GORHAM, KANSAS 67640

PLUGGING CONTRACTOR HALLIBURTON SERVICES LICENSE NO. 5287

ADDRESS 1100 East 8th Street, Hays, Kansas 67601 PHONE # (913) 625-3431

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Joanne Dreshko
(Operator or Agent)

DATE: 11-10-89

RECEIVED
NOV 13 1989
11-13-89
CONSERVATION DIVISION
Wichita, Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
FEB 13 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

November 13, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

BP Exploration Inc.
P.O. Box 4587
Houston, TX 77210

Earl Sutor 1
12-10-20W
SE SE
Rooks County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200