

15-163-03250-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER Nov. 23, 1951 (of this well)

6/88

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR John Petro Co Standard Oil Production Company OPERATORS LICENSE NO. 6854

ADDRESS P.O. Box 4587 Houston, TX 77210 PHONE # (713) 552-8500

LEASE (FARM) Sutor WELL NO. SWD WELL LOCATION C- S/2 NWNWSE COUNTY Rooks

SEC. 13 TWP. 10S RGE. 20W  OIL  (W) TOTAL DEPTH 4236' PLUG BACK TD 4236'

RTKCC

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. D-2978

SURFACE CASING SIZE 10-3/4" SET AT 1630' CEMENTED WITH 1335 SACKS

CASING SIZE 7" SET AT 3823 CEMENTED WITH 200 SACKS

PERFORATED AT None - Open Hole Arbuckle 3823' - 4236'

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Run inside 5-1/2" cement lined tubing with steel bar on sandline. Locate working TD. POOH. Tie onto 5-1/2" tubing at surface and fill with cement. Tie onto 5-1/2" - 7" annulus and fill with cement. Tie onto 7" - 10-3/4" annulus and fill with cement. Cut off casing 4 feet below ground level and cap. State plugger will be on location to supervise.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 9:00 a.m. June 6, 1988

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Joel Stull PHONE # (913) STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION  
5-20-88

ADDRESS Rural Route, Gorham, KS 67640

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. 5287

MAY 20 1988

ADDRESS 1100 East 8th Hays, KS 67601 PHONE # (913) 625-3421

CONSERVATION DIVISION  
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Ray J. Jurga  
(Operator or Agent)

DATE: May 17, 1988

4

State of Kansas



15-163-03250-0000

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

## Kansas Corporation Commission

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

May 20, 1988

AUG 20 '88

WELL PLUGGING NOTICE

EXPIRES

Sutor (SWD)  
C S/2 NW NW SE  
Sec. 13-10S-20W  
Rooks County

Sohio Petroleum Company  
P. O. Box 4587  
Houston, TX 77210


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

  
\_\_\_\_\_  
Shari Feist  
Director  
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200