

15-163-02166-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED FORM CP-1
STATE CORPORATION COMMISSION
6-21-91
JUN 21 1991

WELL PLUGGING APPLICATION FORM
(File One Copy)

CONSERVATION DIVISION
Wichita, Kansas

API NUMBER 15-163-95009- (of this well).
12-13-93

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Tex/Con Oil & Gas Company OPERATOR'S LICENSE NO. 30323 *2/92*

ADDRESS 9401 Southwest Frwy., Houston, TX. 77074 PHONE # (713) 272-5000

LEASE (FARM) Marcotte WELL NO. 1 WELL LOCATION SE NE SW COUNTY Rooks

SEC. 15 TWP. 10S RGE. 20 (E) or (W) TOTAL DEPTH 3766' PLUG BACK TD 3761'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 10-3/4" SET AT 137' CEMENTED WITH 55 SACKS

CASING SIZE 5-1/2" SET AT 3766' CEMENTED WITH 150 SACKS

PERFORATED AT 3752 - 3758' Arbuckle

CONDITION OF WELL: GOOD POOR CASING LEAK Suspect @ 1,100'
JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set cement retainer at 3200'. Squeeze 75 sx of Poz mix below retainer. Spot 100' on top of retainer (13 sx) circulate gelled fluid into well.

Perforate 5-1/2" casing at ± 1200'. Set squeeze packer at 1000'. Attempt to circulate
(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
Cased hole log only (If not explain.)
No open hole logs available

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN July 8, 1991 (Week of)

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Joel Stull - Field Supervisor PHONE # (913) 637-5290

ADDRESS RR 1, Box 37, Gorham, KS. 67640

PLUGGING CONTRACTOR Halliburton LICENSE NO. ~~5287~~

ADDRESS 1100 East 8th, Hays, KS. 67601 PHONE # (913) 625-3431

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Joanne Kreshko
(Operator or Agent)

DATE: 6-19-91

4

cement to surface via 5-1/2" / 10-3/4" annulus (300 sx). Set 100' surface plug inside 5-1/2" casing (13 sx). Casing to be cut below plow depth. A steel cap will be welded on casing stub.



Kansas Corporation Commission

Joan Finney
Governor

Jim Robinson
Chairman

Keith R. Henley
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian J. Moline
General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

June 21, 1991

Tex/.Con Oil & Gas Company
9401 Southwest Frwy.
Wichita, KS 67278

Marcotte 1
SE NE SW
Sec. 15-10-20W
Rooks County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238