


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-051-00228-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 4 Twp. 12 Rge. 19 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE
Lease Owner Trans Era Petroleum, Inc.
Lease Name Merrill Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 12/20/52 19
Application for plugging filed 1/5/53 19
Application for plugging approved 1/5/53 19
Plugging commenced 1/6/53 19
Plugging completed 1/15/53 19
Reason for abandonment of well or producing formation Dry/

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Eldon Petty

Name of Conservation Agent who supervised plugging of this well Yes
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3648 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 190 | None |
| | | | | 5 1/2" | 3643 | 3117' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Plugged back with crushed rock from 3665' to 3635'. Dumped 4 sacks of cement at 3635' with dump bailer. Top of cement 3605'. Filled hole with mud to 190', set rock bridge, dumped 15 sacks of cement, top of cement 140'. Filled hole with mud to 35', set rock bridge, dumped 10 sacks of cement for cap.

RECEIVED
STATE CORP. COM.
1-27-1953

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Herbert R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herbert R. Michaelis
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of January 19 53

My commission expires 2-8-54.

Notary Public.

24-2675-S 2-52-20M

PLUGGING
FILE SEC 4 T 12 R 19
BOOK PAGE 23 LINE 4

Trans Era Petroleum, Inc.
Merrill #1

SW SW NE 4-12-19
Ellis County, Ks.

Total Depth: 3648'
Comm. 12/7/52
Comp. 12/20/52

Casing

Cement

8 5/8" Set @ 190'
5 1/2" Set @ 3643'

135 sacks Portland
50 sacks Lone Star

| Formation | Depth |
|---------------------|-------|
| Clay-Post rock-sand | 100 |
| Shale-shells | 192 |
| Shale | 342 |
| Shale-shells | 827 |
| Sand | 1070 |
| Shale-red bed | 1440 |
| Anhydrite | 1485 |
| Shale | 1840 |
| Salt-shale | 1890 |
| Shale-shells | 1940 |
| Lime-shale | 3352 |
| Lime | 3425 |
| Lime-shale | 3455 |
| Lime | 3598 |
| Lime-shale | 3645 |
| Arbuckle | 3648' |

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

-----*Cora B. [Signature]*-----

Subscribed and sworn to before me this 26th day of December, 1952.

-----*[Signature]*-----
Notary Public

My commission expires: 2-8-54.



1-27-1953
DIVISION

| | | | |
|-----------------|---------|--------|-------|
| PLUGGING | | | |
| FILE | SEC 4 | T 12 | R 192 |
| BOOK | PAGE 73 | LINE 4 | |