


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-051-04233-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 4 Twp. 12S Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW  
Lease Owner Eldorado Refining Company  
Lease Name Merrill Well No. 1  
Office Address 10th Floor, Central Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 4-10-57 19  
Application for plugging filed yes 19  
Application for plugging approved yes 19  
Plugging commenced 4-10-57 19  
Plugging completed 4-10-57 19  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3665 Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with heavy mud to 550 feet.  
First plug set at 550' - cemented with 25 sx. cement through drl. pipe.  
hole filled with heavy mud from 550 feet to 540 feet.  
Second plug set at 40 feet - 1/3 sack of hulls on top of plug - cemented with 10 sacks to surface.



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Frank Hamlin

(Address) \_\_\_\_\_  
SUBSCRIBED AND SWORN to before me this 13th day of May, 19 57

My commission expires 2-22-61  
Dorothy P. Haas  
Dorothy P. Haas, Notary Public, Wichita, Kansas

PLUGGING  
FILE SEC 4 T 12 R 19W  
BOOK PAGE 6 LINE 23

CONTRACTOR'S LOG

COMPANY: Eldorado Refining Co. LOCATION: NE NE NW  
 Section 4-12S-19W  
 CONTRACTOR: Leben Drilling, Inc. Ellis County, Kansas  
 FARM NAME: # 1 Merrill CASING: 8 5/8" @ 325' w/200 sx.  
 ELEVATION: 2511 R.B. COMMENCED: 3-29-57  
 COMPLETED: 4-10-57

...0	..35	Surface Clay & rock	
..35	.115	Sand & shale & shells	
.115	.327	Shale & lime Stks.	
.327	.908	Shale & Red bed	
.908	1115	Sand	
1115	1175	Shale & Red Bed	
1175	1375	Shale & Red Bed	
1375	1429	Shale & Red Bed	
1429	1469	Anhydrite	
1469	1545	Shale	
1545	1775	Shale & Lime	
1775	1885	Shale & Shells	
1885	1930	Lime & Shale	
1930	2030	Lime & Shale	
2030	2130	Lime	
2130	2200	Lime & Shale	
2200	2285	Lime & Shale & Sand	
2285	2365	Lime	
2365	2415	Lime	
2415	2465	Lime	
2465	2585	Lime	
2585	2675	Lime & Shale	
2675	2800	Shale & Lime	
2800	2905	Shale & Lime	
2905	3000	Shale & Lime	
3000	3075	Shale & Lime	TOPS:
3075	3190	Shale & Lime	Anhydrite 1429 (+683)
3190	3260	Shale & Lime	Heebner 3319 (-1207)
3260	3305	Lime & Shale	Toronto 3337 (-1225)
3305	3370	Lime	Lansing 3360 (-1248)
3370	3430	Shale & Lime	Conglomerate 3622 (-1510)
3430	3485	Lime	
3485	3525	Lime	
3525	3575	Shale & Lime	
3575	3630	Lime & Shale	
3630	3665	Total Depth	

State of Kansas }  
 County of Sedgwick } ss:

I, Frank Hamlin, do hereby certify that the above and foregoing is true and correct copy of the Log of the # 1 Merrill, NE NE NW, Section 4-12S-19W, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin  
 Frank Hamlin

Subscribed and Sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 17th day of April, 1957.

Dorothy P. Haas  
 Dorothy P. Haas, Notary Public  
 Wichita, Kansas

My Commission expires: 2-22-61.

5-15-1957

PLUGGING  
 FILE SEC. 4 12 19W  
 BOOK PAGE 6 LINE 23