


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-01248-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis

County. Sec. 4 Twp. 12S Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines NW SE NE - E/2 NE/4

Lease Owner Chief Drilling Co., Inc.

Lease Name Merrill Well No. 1

Office Address P. O. Box 97, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 11-26-60 19

Application for plugging filed 11-26-60 19

Application for plugging approved 11-26-60 19

Plugging commenced 11-26-60 19

Plugging completed 11-26-60 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3696 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	203.28	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1 Wooden Plug set at 600'.

Mixed 20 sacks cement through drill pipe.

1/3 Sack of Hulls, wooden plug set at 180'.

Mixed 15 sacks cement through drill pipe.

1/3 Sack of Hulls, wooden plug set at 40'.

Mixed 10 sacks cement through drill pipe.

STATE CORPORATION COMMISSION

11-28-1960
NOV 2

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address P. O. Box 97, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

V. Richard Hoover, President

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover, President

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 19 60

My commission expires

October 3, 1964

Helen E. Fischer
Helen E. Fischer

Notary Public.

15-051-01248-00-00

WELL LOG

Chief Drilling Co., Inc.
P. O. Box 97
Great Bend, Kansas

No. 1 Merrill
NW SE NE E/2 NE/4 Sec. 4-12S-19W
Ellis County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 11-16-60
Completed: 11-26-60
D & A

Casing Record: 8-5/8" at 203.28' with 150 sacks HA5 Quickset Cement

11-28-1960

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Red Shale & Sand Streak	0	202'	2149' Gr.
Shale	202'	710'	2151' D.F.
Sand	710'	830'	2153' K.B.
Shale	830'	1000'	
Sand	1000'	1150'	
Shale & Shells	1150'	1457'	
Anhydrite	1457'	1501'	
Shale & Shells	1501'	1785'	
Shale & Lime	1785'	2320'	
Lime & Shale	2320'	3122'	
Lime	3122'	3350'	
Shale & Lime	3350'	3391'	
Lime	3391'	3619'	
Shale & Lime	3619'	3644'	
Shale, Lime & Chert	3644'	3675'	
Dolomite	3675'	3696'	
Total Depth	3696'		

<u>FORMATION TOPS</u>	
Anhydrite	1457' (+696)
Topeka	3122' (-969)
Heebner	3350' (-1197)
Toronto	3369' (-1216)
Lansing	3391' (-1238)
Base Kansas City	3619' (-1466)
Conglomerate	3644' (-1491)
Simpson	3664' (-1511)
Arbuckle	3675' (-1522)

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NW SE NE E/2 NE/4 Sec. 4-12S-19W, Ellis County, Kansas to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 26th day of November, 1960.

My commission expires October 3, 1964.

Helen E. Fischer
Helen E. Fischer, Notary Public