

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-051-00575-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec. 4 Twp. 12S Rge. 19W (X) (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW
Lease Owner Leben Drilling, Inc., & Arnell Company
Lease Name Merrill Well No. 1
Office Address 905 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 4, 1957 19
Application for plugging filed August 4, 1957 19
Application for plugging approved August 4, 1957 19
Plugging commenced August 4, 1957 19
Plugging completed August 4, 1957 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	231'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug @ 700' with 25 sacks cement
2nd Plug @ 210' with 25 sacks cement
Top Plug @ 40' with 10 sacks cement.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Frank Hamlin (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 57

My commission expires June 17, 1961

Ruth N. Benjamin
Notary Public.

PLUGGING
FILE SEC A T 12 R 19W
BOOK PAGE 34 LINE 17

15-051-00575-00-00

CONTRACTOR'S WELL LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

COMMENCED:
COMPLETED:

LEBEN-ARTHRELL
LEBEN DRILLING INC.
MERRILL NO 1
NE SE NW SEC 4 12S 19W
ELLIS COUNTY, KANSAS
7-25-57
8-4-57

			FORMATION TOPS
0	285	Shale & Shells	
285	855	Shale & Red Bed	
855	1125	Sand	Anhydrite 1430 (+696)
1125	1310	Shale	Heebner 3337 (-1211)
1310	1430	Shale & Red Bed	Toronto 3354 (-1228)
1430	1479	Anhydrite	Lansing 3376 (-1250)
1479	1865	Shale & Lime	Conglomerate 3637 (-1511)
1865	2320	Lime & Shale	Arbuckle 3656 (-1530)
2320	2920	Lime & Shale	
2920	3060	Shale & Lime	
3060	3320	Lime & Shale	
3320	3365	Shale & Lime	
3365	3645	Lime	
3645	3657	Conglomerate	
3657	3680	Arbuckle	
	3680	ROTARY TOTAL DEPTH D & A	

Set 8 5/8 " surface casing @ 231' w/125 sacks cement and 2 % CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Merrill #1, NE SE NW of Section 4, Township 12 South, Range 19 West, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

BY: Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 7th day of August 1957.

Ruth N. Benjamin
Ruth N. Benjamin-Notary Public

My Commission expires June 17, 1961.

PLUGGING
FILE SEC 4 T. 12 R. 19W
BOOK PAGE 34 LINE 17

RECEIVED
STATE CORPORATION COMMISSION
8-14-1957
AUG 14 1957
CONSERVATION DIVISION
Wichita, Kansas