

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-051-04568-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis

County, Sec. 4 Twp. 12S Rge. 19W (X) (W)

Location as "NE/CNW/SW" or footage from lines W<sup>1</sup>/<sub>2</sub> NW<sup>1</sup>/<sub>4</sub> NE<sup>1</sup>/<sub>4</sub>

Lease Owner Artnell Company & Leben Drilling, Inc.

Lease Name J. J. Merrill Well No. 1

Office Address 533 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-1-58 19

Application for plugging filed 2-1-58 19

Application for plugging approved 2-1-58 19

Plugging commenced 2-1-58 19

Plugging completed 2-1-58 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edlon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	225'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st Plug @ 600 w/20 sacks cement  
2nd Plug @ 210' w/15 sacks cement  
Top Plug @ 40' w/10 sacks cement.

2-5-1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

I, Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin

905 Central Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 19 58

Ruth N. Benjamin  
Ruth N. Benjamin Notary Public.

My commission expires June 17, 1961

PLUGGING  
FILED 4 T. 12 R. 19 W  
BOOK PAGE 81 LINE 27

## DRILLER'S LOG

COMPANY: LEBEN DRILLING, INC. & ARTWELL CO.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: J. J. MERRILL #1  
 LOCATION: W $\frac{1}{2}$  NW NE Sec. 4-12S-19W  
 ELLIS COUNTY, KANSAS  
 COMMENCED: 1-23-58  
 COMPLETED: 2-1-58

0	225	Soil & Shale	
225	350	Blue Shale	
350	685	Shale & Shells	TOPS:
685	925	Shale	
925	1150	Sand	ANHYDRITE 1430
1150	1200	Shale	HEEBNER 3342
1200	1430	Shale & Red Bed	TORONTO 3358
1430	1470	Anhydrite	LANSING -K.C. 3381
1470	1530	Red Bed & Shale	CONGLOMERATE 3648
1530	1720	Shale & Shells	
1720	2265	Shale & Lime	ELEVATION 2129 K. B.
2265	3225	Shale & Lime	
3225	3490	Lime	
3490	3640	Lime	
3640	3680	Conglomerate	
	3680	<u>Rotary Total Depth - D. &amp; A.</u>	

Set 225' of 8 5/8" surface casing with 150 sacks cement and 3% Cacl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the J. J. Merrill #1, located W $\frac{1}{2}$  NW NE of Section 4, Township 12 South, Range 19 West, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By:

*Frank Hamlin*  
 Frank Hamlin

STATE OF KANSAS )  
 COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 7th day of February, 1958.

*Ruth N. Benjamin*  
 Ruth N. Benjamin, Notary Public

My Commission Expires:  
 June 17, 1961 .

2-8-1958

