

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-051-00097-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 21 Twp. 12 Rge. (E) 18 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW
Lease Owner Earl F. Wakefield, et al
Lease Name C. A. Schumaker Well No. 1
Office Address 307 Union Natl. Bk. Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-10 1952
Application for plugging filed 3-11 1952
Application for plugging approved 3-11 1952
Plugging commenced 3-11 1952
Plugging completed 3-11 1952
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3810 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	146.33'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with Heavy Mud from 3810 feet to 150 feet, bridged with Halliburton Plug & 1/2 sack hulls cemented with 15 sacks, heavy mud to 35 feet, bridged with Halliburton Plug & 1/2 sack hulls, cemented to bottom of cellar.

3-22-1952

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Earl F. Wakefield
Address 307 Union National Bank Bldg.,
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
F. S. Barker (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. S. Barker
307 Union Natl. Bk. Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of March 1952

B. James Gaffney
Notary Public.

My commission expires 12-23-54

28-5091-s 8-50-10M

PLUGGING
FILE REC-21T-12R-18W
BOOK ARE-179
LINE VI

15-051-00097-00-00

Schumacher #1
Owner: Earl F. Wakefield, et al
Contractor: Earl F. Wakefield
Comm: 2-27-52 Comp: 3-12-52

SW SW SW 21-12-18
Ellis County, Kansas
Casing: 146.33' of 8 5/8"

Elevation 2177

Surface Sand	10
Shale	105
Sand	125
Shale	510
Shale & Shells	760
Shale & Sand	865
Sand	975
Shale	1460
Anhydrite	1501
Shale	1730
Shale & Shells	1950
Salt	1980
Shale & Shells	2065
Shale & Lime	2200
Lime & Shells	2350
Shale & Lime	2455
Lime & Shale	2550
Lime & Shells	2690
Shale & Lime	2980
Lime & Shale	3052
Shale & Lime	3255
Lime & Shale	3427
Lime	3700
Lime & Shale	3795
Lime	3810
Total Rotary Depth	3810

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

3-22-1952

I hereby certify that the above is a true and correct copy of the log on the Schumacher #1 well located SW SW SW 21-12-18, Ellis County, Kansas.

F. S. Barker

Subscribed and sworn to before me this 20 day of March, 1952.

E. Jeanne Gafney

My Commission Expires: 12-23-54

PLUGGING
FILE SEC 21-12-18
BOOK PAGE 149 LINE 41