

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-051-01306-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County. Sec. 3 Twp. 12S Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines SW NE SE

Lease Owner Glickman - Houston - Nadel & Gussman

Lease Name Nicholson Well No. 1

Office Address 702 S. St. Francis, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-31-61 ~~xxxxxxx62xx~~

Application for plugging filed 12-31-61 ~~xxxxxxx62xx~~

Application for plugging approved 12-31-61 ~~xxxxxxx62xx~~


Plugging commenced 12-31-61 ~~xxxxxxx62xx~~

Plugging completed 1-1 19 62

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, Victoria, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3837 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud up to 480'  
Set plug & cemented w/20 sxs.  
Mud up to 240'  
Set plug & cemented w/20 sxs  
Mud up to 40'  
Set plug & Halls & cemented w/10 sxs  
2 Sxs. in Rat Hole.

RECEIVED  
STATE CORPORATION COMMISSION  
1-17-1962  
JAN 17 1962  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glickman Oil Company

Address 7-02 S. St. Francis, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Milton Glickman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_

P. O. Box 3104, Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 62

My commission expires November 19, 1963

Lorella Schauf Notary Public.



15-051-01306-00-00  
 GLICKMAN OIL COMPANY  
 P. O. Box 3108  
 Wichita, Kansas

DRILLERS WELL LOG

Company: Glickman - Houston - Nadel & Gussman      Location: SW NE SW  
 Farm: Nicholson      Well No. 1      Sec. 3-12S - 19W  
 Commenced: 12-18-61      Elevation: 2220 R. B.  
 Completed: 1-1-62  
 Total Depth: 3837  
 Casing: 8-5/8" @ 245# w/160 sx's.      Production: D & A

Geologist -- Claud Sheats, Jr.

Figures Indicate Bottom of Formations

100	Soil Sand & Shale		
245	Lime & Shale		
305	Shells & Shale		
630	Shale		
635	Red Bed		<u>TOPS</u>
1220	Red Bed - Shale & Sand Streaks		
1390	Shells & Shale	Anhydrite	1540
1540	Shale & Shells	Topeka	3204
1580	Anhydrite	Heebner	3433
1890	Shale & Lime	Toronto	3452
2250	Shale w/lime Streaks	Lansing	3475
2830	Lime & Shale	Base Kansas City	3714
2935	Shale & Lime	Conglomerate	3754
3007	Lime & Shale	Arbuckle	3812
3055	Shale & Lime		
3267	Lime		
3342	Lime & Shale		
3380	Lime & Chert		
3610	Lime		
3660	Lime - Shale & Chert		
3715	Lime		
3766	Lime - Shale & Chert		
3786	Cherty Conglomerate		
3812	Conglomerate		
3837	Arbuckle		
3837	RTD		

RECEIVED  
 STATE COOPERATION COMMISSION  
 1-17-1962  
 JAN 17 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Milton Glickman, of the Glickman Oil Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Nicholson #1

Milton Glickman  
 Milton Glickman      Partner

Subscribed and sworn to before me this 8th day of January 1962

Lorella Schauf  
 Lorella Schauf      Notary Public

My Commission Expires: November 19, 1963

