


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-04655-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec 21 Twp. 12 Rge. 18 (E) (W) W
Location as "NE/CNWxSWx" or footage from lines C E L SE NW
Lease Owner C-G Drilling Co & Houston Petroleum Co
Lease Name Blender Well No. 1
Office Address 107 Rule Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 22 1960
Application for plugging filed November 22 1960
Application for plugging approved November 22 1960
Plugging commenced November 22 1960
Plugging completed November 22 1960
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3714 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	186.89'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 550'. Set plug. Put in 20 sacks cement. Filled to 180'. Set plug. Put in 20 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
11-29-1960
NOV 29 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jay H. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of November, 1960

My commission expires May 20, 1963 Vicky Jacobs Notary Public.



15-051-04655-00-00

WELL LOG

OPERATOR C-G Drilling Co. & Houston Petroleum Co. SEC. 21-12-18W
 WELL NAME Blender #1 LOC. C E L SE NW
 TOTAL DEPTH 3714' COUNTY Ellis
 COMM. November 14, 1960 COMP. November 22, 1960 STATE Kansas
 RIG NO. 1 ELEVATION 2149' R.B.

CASING: Ran 186.89' (9 jts.) 8-5/8" OD Surface Casing. PRODUCTION: D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	980	Shale		
980	1090	Sand		
1090	1300	Shale-Shell-Red Bed		
1300	1428	Red Bed		
1428	1470	Anhydrite		
1470	1960	Shell-Shale		
1960	2055	Shale-Streak Lime		
2055	2435	Shale-Lime		
2435	2565	Lime	0° - 2500	
2565	3225	Lime-Shale	0° - 2750	
3225	3290	Shale-Lime	0° - 3000	
3290	3435	Lime-Shale	0° - 3250	
3435	3540	Lime	0° - 3500	
3540	3591	Lime-Shale		
3591	3690	Lime		
3690	3714	Lime-Shale		

RECEIVED
 STATE CORPORATION COMMISSION
 11-29-1960
 NOV 29 1960

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway
 Jay H. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 28th day of November, 1960.

My commission expires:
 May 20, 1963

Vicky Jacobs
 Vicky Jacobs - Notary public