

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-04488-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ellis County, Sec. 15 Twp. 12 Rge. 18 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE $\frac{1}{4}$ SE $\frac{1}{4}$ NE $\frac{1}{4}$

Lease Owner Dizdar Investment Co.

Lease Name Baker Well No. 1

Office Address McAllen, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 5-21 19 51

Application for plugging filed 5-21 19 51

Application for plugging approved 5-21 19 51

Plugging commenced 5-21 19 51

Plugging completed 5-21 19 51

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3755 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 152' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 145 feet. 15 sacks cement placed on plug.
Fill hole to 40' of surface with mud. Pushed plug to 40'
and placed 10 sacks of cement on plug.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Glenn R. Nye Drilling Company
Address Drawer 30
Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.

Glenn R. Nye (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glenn R. Nye
Drawer 30 Hays, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9 day of June, 19 51

My commission expires May 9, 1953



John L. Baize
Notary Public

PLUGGING
FILE SEC 15 T 12 R 18 W
BOOK PAGE 84 LINE 24

6-11-1951
JUN 11 1951
CONSERVATION DIVISION
WICHITA, KANSAS

15-051-04488-00-00

Company: Dizdar Investment Company

Farm: Baker No. 1

Contractor: Glenn R. Nye Drilling Company

Location: NE SE NE Sec. 15-12-18W

Commenced: May 10, 1951

Ellis County, Kansas

Completed: May 21, 1951

Casing Record: 8 5/8" set at 152'

(Figures below indicate bottoms)

| | | |
|-----------------|------|-----------------------|
| surface soil | 20 | |
| post rock | 60 | |
| sand | 70 | |
| blue shale | 130 | |
| blue shale | 152 | |
| blue shale | 160 | |
| shale & shells | 215 | |
| blue shale | 425 | |
| shale & shells | 540 | |
| shale & shells | 610 | |
| shale & sand | 745 | |
| sand | 855 | |
| shale & shells | 930 | |
| sand | 1085 | |
| red bed & shale | 1175 | |
| red bed & shale | 1421 | |
| anhydrite | 1450 | |
| anhydrite | 1458 | |
| shale & shells | 1625 | |
| shale & shells | 1820 | |
| shale & salt | 1920 | |
| shale & lime | 2005 | |
| shale & lime | 2120 | |
| shale & lime | 2250 | |
| lime & shale | 2295 | |
| lime & shale | 2420 | |
| lime & shale | 2435 | |
| shale & lime | 2520 | |
| shale & lime | 2685 | |
| shale & lime | 2795 | |
| shale & lime | 2930 | |
| shale & lime | 3015 | |
| shale & lime | 3170 | |
| shale & lime | 3250 | |
| lime & shale | 3300 | |
| lime & shale | 3335 | Top Heebner 3364 |
| lime & shale | 3400 | Top Lansing K.C. 3406 |
| lime | 3470 | |
| lime | 3520 | |
| lime | 3562 | |
| lime | 3614 | |
| lime | 3665 | Top Conglomerate 3670 |
| lime | 3718 | |
| lime | 3755 | T. D. |

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLENN R. NYE DRILLING COMPANY

By Glenn R. Nye

6-11-1951

STATE OF KANSAS)
ELLIS COUNTY) SS

Subscribed to and sworn to before me, a notary public, in and for said County and State this 9th day of June, 1951.

Com. Nye
Notary Public

My Commission Expires. May 9, 1953

PLUGGING
FILE SEC. 15 T. 12 R. 18W
BOOK PAGE 84 LINE 24

