

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Ellis County, Sec. 15 Twp. 12 Rge. 18 (E) W (W)

Location as "NE/CNW&SWK" or footage from lines SE SW NE

Lease Owner Shields Oil Producers

Lease Name Baker Well No. 1

Office Address Shields Bldg., Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed July 1 19 59

Application for plugging filed July 1 19 59

Application for plugging approved July 1 19 59

Plugging commenced July 1 19 59

Plugging completed July 1 19 59

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3725 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	210'	Cmtd. w/135sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill w/heavy mud to 500'  
Set bridging plug @ 500'  
Dump 20 sax cement thru drill pipe on plug  
Fill w/heavy mud to 180'  
Set bridging plug @ 180'  
Dump 20 sax cement thru drill pipe on plug  
Fill w/heavy mud to 40'  
Set bridging plug @ 40'  
Dump 10 sax cement to cellar

7-10-1959  
COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Oil Producers

Address Shields Bldg., Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

R. J. Shields (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. J. Shields*

Shields Bldg., Russell, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 8th. day of July, 19 59

My commission expires March 6, 1961

*Harriet V. Peterson*  
Notary Public.

PLUGGING  
FILE SEC. 15 T. 12 R. 18 W  
BOOK PAGE 50 LINE 16




# Shields

Russell, Kansas

## WELL LOG

Operator: Shields Oil Producers  
 Well: Baker #1  
 Commenced: June 22, 1959  
 Completed: July 1, 1959  
 Contractor: Shields Drilling Co., Inc.

Well Description SE SW NE  
 Sec. 15-12S-18W  
 Ellis County, Kansas



CASING RECORD		
Size	Run	Pulled
8 5/8"	210'	Cmtd. w/135 sax

Elevation: 2169' RB  
 Treatment:  
 Production: D & A

Tops	Formation	Elevation
	Topeka	3130'
	Heebner	3378'
	Toronto	3398'
	Lansing-KC	3424'
	Simpson	3690'
	Arbuckle	3704'

Figures Indicate Bottom of Formations

Shale	212'
Shale; Shells w/Sand Streaks	682'
Sand; Shale; Red Bed	1442'
Anhydrite	1485'
Shale & Shells	1695'
Shale & Lime	1830'
Shale w/Lime Streaks	2120'
Lime & Shale	3170'
Lime	3725' RTD

### NOTES

- DST #1 3478'-3535' Tool open for 30 min. w/weak blow for 7 min. Rec. 6' mud. All pressure 0#.
- DST #2 3685'-3725' Tool open for 30 min. w/weak blow for 11 min. Rec. 6' mud. All pressure 0#.

**PLUGGING**  
 FILE SEC 15 T 18 R 18 W  
 BOOK PAGE 50 LINE 16