

15-163-02090-0000

CHAMPLIN PETROLEUM COMPANY

EARL #3

NW - NW - NE
Sec. 13 - T 10S - R 20W
Rooks County, Kansas

CASING RECORD:

8-5/8" - 32# Spang. - 250' cemented w/ 150 sacks
5 1/4" - 14# O.D. - 3762' cemented w/ 175 sacks

FORMATION RECORD:

0' - 254'	Surface Clay - Sand
254' - 505'	Shale
505' - 700'	Shale - Shells
700' - 800'	Sand
800' - 1,100'	Redbed - Shells
1,100' - 1,220'	Sand
1,220' - 1,370'	Sand - Shale - Shells
1,370' - 1,640'	Shale - Shells
1,640' - 1,675'	Anhydrite
1,675' - 1,740'	Redbed - Shale
1,740' - 2,145'	Shale - Shells - Salt
2,145' - 2,995'	Lime - Shale
2,995' - 3,100'	Shale
3,100' - 3,485'	Lime - Shale
3,485' - 3,729'	Lime
3,729' - 3,759'	Cong. - Simpson
3,759' - 3,763'	Simpson - Arbuckle
3,763'	TOTAL DEPTH

FORMATION TOPS:

3,470'	Top Lansing
3,761'	Top Arbuckle

RECEIVED
STATE CORPORATION COMMISSION
01-14-80
JAN 14 1980

CONSERVATION DIVISION
Wichita, Kansas