

**KANSAS DRILLERS LOG**

Form No. 1  
 State Geol. Survey  
 Applies on this well.

**ORIGINAL**

S. 32 T. 10 R. 20 <sup>EW</sup>

API No. 15 — 163 — 21,037 - 0000  
 County Number

Loc. SE NE SW

County Books

Operator  
 Sid Tomlinson

Address Box 594 Twin Falls, Id. 83301


Well No. #1 Lease Name Keller

Footage Location  
 1070 SW/4 feet from (N) 25 line 330 feet from (E) 1/4 line

Principal Contractor Geologist  
 Revlin Drilling, Inc. Jerry Jesperson

Spud Date Total Depth P.B.T.D.  
 3-8-80 3820' R.T.D. 3803

Date Completed Oil Purchaser  
 5/22/80 Mobil Oil



Elev.: Gr. 2131  
 DF KB 2136

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28#	278'	Common	175	3% c.c.
Production	7 7/8	4 1/2	9.5#	3819'	Common	175	3/4 of 1% CFR2 10# salt 5% gilsonite

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3	jets	3546-50 3567-71 3602-06

**TUBING RECORD**

Size	Setting depth	Packer set at
2 3/8	3788'	

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
7000 gals. 15% NE acid	3546-3606

**INITIAL PRODUCTION**

Date of first production 5/6/80	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 38 bbls. Gas -0- MCF Water 20 bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s) 3546-50, 3567-71, 3602-06

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-322-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

RECEIVED  
 STATE CORPORATION COMMISSION  
 6-1-82  
 CONSERVATION DIVISION  
 Wichita, Kansas

Operator **Sid Tomlinson** *AWC* *MC* DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:


Well No. **1** Lease Name **Keller** Oil

s 32 r 10 R 20  W

**WELL LOG**  
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.  
 SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 3400-60' 30/60/60/120 Rec 1040' salt water FP 53-454 ISIP 1040 FSIP 1008				
DST # 2 3474-3515 30/60/60/120 Rec 150' muddy wtr. w/few speck oil (40% SW, 59 1/2% mud, 1/2% oil) FP 32-116 ISIP 695 FSIP 684				
DST #3 3525-75 30/60/60/120 rec 575' gas in pipe, 250' mud & gas cut oil (10% gas, 70% oil, 15% mud, 5% wtr.) FP 32-127 ISIP 674 FSIP 663				
DST #4 3580-3630 30/60/45/90 weak blow & died. rec 45' mud w/show of oil FP 36-42 ISIP 808 FSIP 464				
Ran Gamma Ray/Neutron/Laterlog			Anhydrite Heebner Lansing Arbuckle	1586 3370 3408 3769

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

<b>Date Received</b>	 Signature <b>Sid Tomlinson, Oil Producer Operator</b> Title <b>July 3, 1980</b> Date
----------------------	--