

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-163-00651-0000

API NUMBER January, 1950

LEASE NAME Sutor

WELL NUMBER 1

4950 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 13 TWP. 10S RGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed 1-14-50

Plugging Commenced 10-29-90

Plugging Completed 10-29-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Petroleum, Inc.

ADDRESS 301 N. Main, Suite 900 Wichita, Ks 67202

PHONE# (316) 291-8282 OPERATORS LICENSE NO. 5238

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 29, 1990 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation L-KC Arb-open hole 3768 3773
 Depth to Top 3476 Bottom 3687 T.D. 3773

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	316	None
				5 1/2	3769	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perf 2 holes at 1640' and 480'. Pumped down 5 1/2" csg. with 315 sx. 65/35 Poz, 10% gel, 1/4#/sx flowseal and 400# hulls, M.P. 1000#, S.I.P. 400#, Pumped down 8 5/8" csg. with 35 sx. 65/35 Poz, 10% gel, 1/4#/sx flowseal and 100# hulls, M.P. 1000#, S.I.P. 600#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B.J. Titan Services License 11-7-90

Address P.O. Box 69, Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Paul Kreutzer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Kreutzer

(Address) 301 N. Main - Suite 900, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 6 day of November, 19 90



Sherry Fraser
 Notary Public