

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-02101-00-00
LEASE NAME SUTOR 'A' #7

RECEIVED
12-21-01
DEC 21 2001
WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

WELL NUMBER 'A' #7
4180
4620 Ft. from S Section Line
4950 Ft. from E Section Line
SEC. 13 TWP. 10S RGE. 20W (E) or (W)
COUNTY ROOKS
Date Well Completed 2-22-1957
Plugging Commenced 12-18-2001
Plugging Completed 12-18-2001

LEASE OPERATOR T&P OIL&GAS LLC.ATTN: TOM RAGUSA
ADDRESS OVERLAND PARK, KS. 66204
PHONE (785) 749-0672 OPERATORS LICENSE NO. 32500

Character of Well csg lesks
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 12-17-2001 (date)
by HERB DEINES (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____
Producing Formation ARB Depth to Top 3717 Bottom 3721 T.D. 3721

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface	shale - sd	g.l	304	8 5/8	304	none
arb	dolomite	gl	3717	5 1/2	3717	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. ran tbg to 2700' tbg started floating so pumped 100 sx and 500# hulls pulled tbg to 1725' pumped 150 sx & 300# hulls. cmt circulated to pit. Lay tbg out, pumped though swage, had hose on the braden head, cir cmt from b h, closed valvae on b h mix 40 sk cmt, standing at 200 psi. (used 290 sx 60/40 10% gel, 800# hulls.)

Name of Plugging Contractor Swift Cmtg For T&P License No. 32500
Address 7801 Metcalf Ave - Overland park, KS. 66204

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ATTN: TOM RAGUSA

STATE OF KANSAS COUNTY OF ROOKS, s.s.
ROBERT A. WAHLMEIER (Consultant).

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filled the the same are true and correct, so help me God.

(Signature) Robert A. Wahlmeier
(Address) 2213 Virginia Drive Hays, Ks 67601

SUBSCRIBED AND SWORN TO before me this 19 day of December, 19 2001

My Commission Expires: July 31 - 2002 Notary Public

