

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Rooks SEC. 13 TWP. 10S RGE. 20 xE/W  
 Location as in quarters or footage from lines:  
1570; FNL & 1735' FEL of NE/4


Lease Owner Phillips Petroleum Company  
 Lease Name Earl-C Well No. D10 10 *ADD KCC*  
 Office Address Box 287, Great Bend, Kansas 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): Disposal  
 Date Well Completed May 9, 1951  
 Application for plugging filed September 16, 1982  
 Plugging commenced October 5, 1982  
 Plugging completed October 11, 1982  
 Reason for abandonment of well or producing formation Would not take water

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel  
 Producing formation Cedar Hills Depth to top 935 bottom 1301 T.D. 4190  
 Show depth and thickness of all water, oil and gas formations. PBTD 1301'

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Water	0'	235'	8 5/8"	235'	-0-
Production	Oil & Wtr	0'	3862	5 1/2"	3862	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet for each plug set. On 10-5-82 MIRU well service unit and pulled 14 jts and 1 piece 2 7/8" OD Tubing. (442.37') Conn. tank truck to 5 1/2" csg and pmpd 38 BW @ 1 BPM @ 450 PSI. On 10-8-82 conn Halliburton to 5 1/2" csg & pmpd 25 sx 50-50 Pozmix w/6% gel. Max press 550 PSI @ 3 BPM. ISIP 100 PSI. Released Halliburton. Cut off 8 5/8" & 5 1/2" csg 4' below GL. Fill 5 1/2" & 8 5/8" annulus w/1 sk cmt. Weld on plate. Well P&A 10-8-82.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer Area Mgr.  
Box 287, Great Bend, Kansas 67530  
 (Address)



SUSCRIPTION AND SWORN TO before me this 11th day of October, 19 82

Velma L. Mog  
 Notary Public.

My Commission expires: February 15, 1984

RECEIVED  
 OCT 13 1982  
 10-13-82  
 CONSERVATION DIVISION  
 Wichita, Kansas