

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rooks County, Sec. 13 Twp. 10S Rge. 20 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SE NE SE

Lease Owner Sohio Petroleum Company

Lease Name Sutor "A" Well No. 2

Office Address Box 673, Russell, KS 67665

Character of Well (Completed as Oil, Gas or Dry Hole)

oil

Date Well completed July 25 1949

Application for plugging filed August 21 1978

Application for plugging approved August 22 1978

Plugging commenced August 31 1978

Plugging completed September 20 1978

Reason for abandonment of well or producing formation
depleted

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3925'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1620'	None
				5-1/2"	3923'	2585'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Push plug to 3418', sand back to 3200'; dump 4 sx cement to 3170'. Shot pipe at 2583', pipe loose. Pulled 80 jts. Pumped 20 sx gel, rubber plug, 50 sx 50-50 Poz with 2% gel, 8 sx gel, and 25 sx 50-50 Poz. Well plugged at 1:05 P.M., 9-20-78.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF KANSAS COUNTY OF RUSSELL, ss.

W. H. Ward (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

W. H. Ward


Box 673, Russell, KS 67665

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of October, 1978

My appointment expires 9-28-79

Juanita Valentine Notary Public.



RECEIVED
STATE CORPORATION COMMISSION
10-18-78
OCT 18 1978

CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S VERIFIED LOG

Operator Sohio Petroleum Company Farm Name Sutor Well No. 2
 Location SE NE SE, Sec. 13-10-20W
 Pool Name Berland County Rooks State Kansas
 Commencement Date 6/20/49 Completion Date 7/3/49

LOG OF WELL

Depth		Formation	Deviation from Vertical (Degrees)	Remarks
From	To			
0	90	Sand, clay		Elevation: 2229'
90	995	Shale, sand		
995	1040	Pirites iron		
1040	1614	Shale, sand		
1614	1620	Anhydrite		8-5/8 w/800 sx.
1620	1940	Shale, red bed		@ 1620
1940	2420	Shale, shells		
2420	3530	Shale, lime		
3530	3680	Lime		
3680	3755	Cherty lime		
3755	3830	Lime		
3830	3905	Cherty lime		
3905	3925	Lime		5 1/2" w/200 sx. @ 3923'

PBTD: 3836' CIB

Open Perforations:
 3776-82' (Arbuck
 3672-76' }
 3658-64' } LKC
 3621-47' }
 3603-08' }

2 7/8" tubing stuck in well at 3927'

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 22 1978
 CONSERVATION DIVISION
 Wichita, Kansas

Continued on Reverse Side