


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rooks County, Sec. 13 Twp. 10 Rge. 20 (X) W. (W)  
Location as "NE/CNW/SW" or footage from lines C E/2 SW NW  
Lease Owner Petroleum, Inc.  
Lease Name Sutor Well No. 8  
Office Address Route 2, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed May 27 1958  
Application for plugging filed May 27 1958  
Application for plugging approved May 27 1958  
Plugging commenced May 27 1958  
Plugging completed May 27 1958  
Reason for abandonment of well or producing formation No producible zones

If a producing well is abandoned, date of last production None 19     
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3804 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	275'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet for each plug set.

Mud up with heavy mud to 550' followed by wooden plug. Placed 20 sacks cement through drill pipe on to plug. Mud up to 240', pushed down 1/2 sack hulls to 240' followed by wooden plug. Placed 20 sacks cement on top of plug. Mud up to 40' and placed 1/2 sack hulls at 40' followed by wooden plug and 10 sacks cement to base of well cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
6-3-58  
JUN 3 1958

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Garvey Drilling Company  
Address Route 2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Don Searle (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle  
Route 2, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of June 1958

My commission expires July 11, 1960

John A. Brown  
Notary Public.

PLUGGING  
FILE SEC 13 T 10 R 20 W  
BOOK PAGE 103 LINE 34

# WELL LOG

15-163-03085-0000

COMPANY PETROLEUM INCORPORATED

SEC. 13 T. 10 R. 20

FARM SUTOR

NO. A-8

LOC. E/2 SW NW


TOTAL DEPTH 3804'

COUNTY ROOKS CO., KANS.

COMM. 5-15-58

COMP. 5-27-58

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 275' W/200 Sax

ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

50	Clay & Sand
1420	Shale
1635	Shale & Shells
1680	Anhydrite
2075	Shale & Shells
2275	Shale & Lime Streaks
2515	Shale & Lime
2680	Lime & Shale
3260	Shale & Lime
3750	Lime
3759	Conglomerate & Chert
3804	Lime & Chert

RECEIVED  
STATE CORPORATION COMMISSION

JUN 3 1958

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 13 T. 10 R. 20  
BOOK PAGE 103 LINE 34

State of KANSAS

County of BARTON

SS:

I, L. J. WEBER

of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #8 SUTOR A well

Subscribed and sworn to before me this 29th day of May 19 58

My Commission Expires: July 11, 1960

*L. J. Weber*

*Delbert Brown*  
NOTARY PUBLIC