

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-163-20323-0000

API NUMBER Drilled 1970

LEASE NAME Brueggeman

WELL NUMBER 9

3930 ⁶ FT. from S Section Line
 RT KCC

4340 FT. from E Section Line

SEC. 15 TWP. 105 RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 9-70

Plugging Commenced 8-25-88

Plugging Completed 8-29-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Union Pacific Resources Company

ADDRESS 1000 Louisiana, Suite 3000, Houston, TX 77002-5016

PHONE# (713) 654-2500 OPERATORS LICENSE NO. 6417

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Aug. 11 (approx) (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle/LKC Depth to Top 3493' Bottom 3698' T.D. 3756'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Completed	From	To	Size	Put in	Pulled out
	<u>NOV 7 1988</u>					
	<u>11-7-88</u>			<u>8-5/8"</u>	<u>253'</u>	<u>none</u>
				<u>4-1/2"</u>	<u>3755'</u>	<u>none</u>

RECEIVED
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RU Halliburton and pump 5 sx hulls and 150 sx 60-40 Pozmix w/6% gel and 3% CaCl down casing. Held 150# pressure. Pump 20 sx down 8-5/8". Total 170 sx. KCC representative on location Gilbert Scheck. Cut off Bradenhead and weld on steel plate. Cement to top of casing, bury cement, fill cellar and level location. Well is P & A.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address Hays, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Union Pacific Resources Company

STATE OF Texas COUNTY OF Harris, ss.

Marilyn Day (Employee of Operator) or ~~(Operator)~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Marilyn Day

(Address) 1000 Louisiana, Suite 3000, Houston, TX 77002

SUBSCRIBED AND SWORN TO before me this 31st day of October, 19 88



Adela Zavala
 Notary Public

Commission Expires: 5-6-91

DRILLERS LOG

No. 9 Brueggeman

CASING RECORD:

8 5/8" @ 253'
w/175 sx cement

4 1/2" @ 3755'
w/600 sx cement

TOTAL DEPTH: 3756'

COMPANY: Champlin Petroleum Company

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: September 11, 1970

COMPLETED: September 21, 1970

DESCRIPTION:

NE SW NW
15-10S-20W
Rooks County,
Kansas

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil, Clay	0	50	
Clay & Shale	50	253	
Shale, Shells, Sand	253	900	
Shale & Sand	900	1082	
Sand	1082	1329	
Shale	1329	1612	
Anhydrite	1612	1652	
Shale	1652	2065	
Shale & Lime	2065	3208	
Lime	3208	3722	
Lime, Arbuckle, Chert	3722	3756	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 23 day of September, 1970.



Virginia K. Albert
Notary Public

My Commission Expires:

July 23, 1974