

LEASE NAME MARCOTTE

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1
1650 Ft. from S Section Line
2970 Ft. from E Section Line

LEASE OPERATOR TEX/CON Oil & Gas Company

SEC. 15 TWP. 10S RGE. 20 (E) (W)

ADDRESS 9401 Southwest Freeway, Houston, TX. 77074

COUNTY Rooks

PHONE# (713) 272-5000 OPERATORS LICENSE NO. 30323

Date Well Completed 12-23-43

Character of Well Oil

Plugging Commenced 8-11-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-12-91

The plugging proposal was approved on _____ (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3752' Bottom 3758' T.D. 3766'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	3752'	58'	10-3/4"	137'	0
				5-1/2"	3766'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perfed csg @ 1680' & @ 950'. RIH w/tbg to 2340' (hit rough spot @ 1570' & 1770'). Spotted 175 sxs of 60/40 Poz mix. Pulled up to 1680' & spotted additional 250 sxs cmt. to circ. to surface. POOH w/tbg & WOC. RIH w/tbg to TOC @ 420'. Spotted 25 sxs cmt @ 420' & circ. to surface. POOH w/tbg. Tied onto 5 1/2" csg @ surface & squeezed w/5 sxs cmt. Hooked up to 8-5/8" annulus & squeezed with 55 sxs cmt. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address 1100 East 8th St., Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TEX/CON Oil & Gas Company


STATE OF TEXAS COUNTY OF Harris, ss.

Cynthia Arnold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Cynthia Arnold

(Address) 9401 Southwest Freeway, Houston, TX 77074

RECEIVED
 STATE CORPORATION COMMISSION
 SUBSCRIBED AND SWORN TO before me this 18th day of Sept., 19 91



Dennis R. Morales
 Notary Public

SEP 23 1991
 09-23-91
 My Commission Expires:
 CONSERVATION DIVISION
 Wichita, Kansas