

15-051-01263-00-00  
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_  
LOCATION NW SE SE  
SEC. 30 TWP. 12 RGE. 17 W

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Karlin "D"

Operator K & NE Drg Co Address Wichita, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3675 Feet.

Plugging Contractor same

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_  
(Describe briefly the manner in which the well was plugged)

8 5/8" at 167' circulated with cement.

Gunned pits, circulated hole with heavy mud. set cementing plug at 400' ,  
displaced 20 sax cement tthrough drill pipe at 400' , heavy mud to  
40' , set cementing plug, 1/2 sack hulls and 10 sax cement to bottem  
cellar.

Edwin Petty  
District Conservation Agent  
Date 3-4-57

**PLUGGING**  
FILE SEC 30 T. 12 R. 17W  
BOOK PAGE 147 LINE 8

3-12-1957