

15-051-21351-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

RECEIVED
STATE CORPORATION COMMISSION
10-20-1977
OCT 20 1977

CONSERVATION DIVISION
Wichita, Kansas (for Division's well)

Operator's Full Name Icer Addis

Complete Address P. O. Drawer 8038, Wichita, Kansas

Lease Name Karlin Well No. 1

Location C S/2 SW SE Sec. 30 Twp. 12 Rge. (E) (W) 17

County Ellis Total Depth 3677'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated Left as fresh water well.

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 6:30 P Day 14 Month 10 Year 1977

The above well was plugged as follows:

RTD 3677' 8 5/8 csg set 208' cwc 150 sk. Flg. Mat. 50-50 poz 48 total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 180' set 30 sk cmt plug thru drill pipe. Filled hole with heavy mud & welded steel cap on 8 5/8 csg.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-20-77
INV. NO. 6056-W

Signed: Leo Messing
Well Plugging Supervisor