

15-051-01308-00-00

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION  
3-7-1961  
MAR 7 1961  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: SW SW NW Sec. 4 Twp. 12 Rge. 18 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3684

I have this date completed supervision of plugging of:

Lease Name: Schermer Well No. 1

Operator's Full Name: D. G. Hansen

Complete Address: Box 195 Logan, Kansas

Plugging Contractor: C & G Drg Co

Address: Wichita, Kansas License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A ☒

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No ☒

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 9:30AM Day 23 Month 2 Year 61

The above well was plugged as follows:

8 5/8" 183' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 550', displaced 20  
sax cement through drill pipe, heavy mud to 180', set plug and 20 sax  
cement through drill pipe, heavy mud to 40', set cementing plug, 1/2 sack  
hulls and 10 sax cement to bottom cellar.

Signed: *Edson Letty*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

**INVOICED**  
DATE 3/14/61  
INV. NO. 2805-W