

15-051-20789-00-00

KANSAS

Form CP-3
Rev. 6-4-68

R STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-17-1971
DEC 17 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Vincent Oil Corporation
Complete Address 719 Union Center Bldg., Wichita, Kansas
Lease Name Johnson Well No. 1
Location NE NE SE Sec. 4 Twp. 12 Rge. (E) (W) 18
County Ellis Total Depth 3730'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Murfin Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 8 P Day 14 Month 12 Year 1971

The above well was plugged as follows:

RTD 3730' 8 5/8 csg set at 200' cwc. Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bio Z. Messing
Well Plugging Supervisor

DATE 12/17/71
INV. NO. 4832-W