

15-051-00574-00-00
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NE NE SW

SEC. 4 TWP. 12 RGE. 18

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Schermer Schermer

Operator Sierra ~~Bot Inc~~ + Oil Trading Address Wichita, Kans 420 W Doug.

Field _____ County Ellis

Total Depth 3650 Feet.

Plugging Contractor same

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 203' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug

at 650', displaced 20 sax cement through drill pipe, heavy mud to

195', set cementing plug, hulls and 15 sax cement displaced through

drill pipe, heavy mud to 40', set cementing plug, 1/2 sack

hulls and 10 sax cement to bottom cellar.

District Conservation Agent

Date 7-24-57

PLUGGING
FILE SEC. 4 T. 12 R. 18 W
BOOK PAGE 31 LINE 16

RECEIVED
STATE CORPORATION COMMISSION
7-26-1957
JUL 26 1957
CONSERVATION DIVISION
Wichita, Kansas