

15-051-00911-00-00
DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 127-15

LOCATION NE-NE-NW

SEC. 4 TWP. 12 RGE. 18W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Schermer

Operator Waxby & Bethwell-Inc Address #2003 Phil Tower Bldg - Tulsa - 3 - Okla

Field _____ County Ellis

Total Depth 3650 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 13 7/8 - 138 ft - cemented all around
5 1/2" casing set at 3650 & cemented with 200 cement.
Land Well Plug set at 3406 ft - Top Perforations 337 ft
Filled hole back from 3406 to 3360 & put in 4 sacks cement
with Blump Bailer - Shot off & recovered 2600 ft of 5 1/2" casing
Filled hole with mud to 135 ft - Set Plug & 25 sacks cement on
top - Surface Plug 20 ft below the surface & 10 sacks cement.
Well made some Oil on the test
Carl Miller - Pipe Puller

C. H. Stouffer
District Conservation Agent
Date 8-31-47

PLUGGING
FILE SEC 4 T 12 R 18W
BOOK PAGE 127 LINE 15