

15-051-00973-00-00
DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 26-21

LOCATION NE NE NE

SEC. 6 TWP. 12 RGE. 18

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease Balls

Operator Heathman Drg Co Address Wichita, Kans

Field _____ County Ellis

Total Depth 3695 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 126' circulated with cement - 5 1/2" at 3665'
with 75 sax cement behind.

Filled with sand to 3660', set 5 sax cement with dump bailer,
pulled 2882' 1 1/2", filled with heavy mud to 135', set rock
bridge and 15 sax cement, filled with heavy mud to 35',
set rock bridge and 10 sax cement to bottom cellar.

RECEIVED
Conservation Div.
9-21-1950
SEP 21 1950

STATE CORPORATION
COMMISSION
KANSAS

Edna Lee
District Conservation Agent

Date 9-16-50

PLUGGING
FILE SEC. 6 T L R 192
BOOK PAGE 26 LINE 21