


15-051-20111-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

County. Sec. 4 Twp. 12 Rge. (E) 18 (W)  
Location as "NE/CNW/SW" or footage from lines SE NW NW  
Lease Owner Allison & Black  
Lease Name Johnson "B" Well No. 1  
Office Address 1415 Wichita Plaza- Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry  
Date well completed 9-3- 1967  
Application for plugging filed 9-3 1967  
Application for plugging approved 9-3 1967  
Plugging commenced 4:00 AM 9-3 1967  
Plugging completed 6:45 AM 9-3 1967  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production none 19     
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation none Depth to top     Bottom     Total Depth of Well 3722 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Rock & Shale		0	216	8 5/8" ID	215	

RECEIVED  
SEP 6 1967  
9-6-1967  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet for each plug set.

Ran 720' drill pipe in hole and cemented with 75 sacks - 210'  
drill pipe at 210' with 25 sacks  
0 to 40' with 11 sacks. Hole plugged with Pump Truck.  
2 sacks in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & B Drilling, Inc.  
Address 548 Petroleum Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss. Bill Lahar

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar

548 Petroleum Building - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of September, 1967

Alma A. Meier

Notary Public.



15-051-20111-00-00  
B & B DRILLING, INC.

548 Petroleum Building

Wichita, Kansas 67202

September 5, 1967

DRILLERS LOG

Re: #1 Johnson "B"  
SE NW NW  
Section 4-12S-18W  
Ellis County, Kansas

COMPANY: Allison & Black  
CONTRACTOR: B & B Drilling, Inc.  
TOTAL DEPTH: 3722'  
COMMENCED: August 26, 1967  
COMPLETED: September 3, 1967

0	20	Rock
20	216	Shale
216	235	Shale
235	850	Shale & Red Bed
850	1110	Shale & Sand
1110	1305	Shale & Sand
1305	1372	Shale
1372	1413	Anhydrite
1413	1486	Shale
1486	1629	Shale & Lime
1629	2000	Shale & Lime
2000	2170	Shale & Lime
2170	2405	Lime & Shale
2405	2570	Lime & Shale
2570	2820	Lime & Shale
2820	3060	Shale & Lime
3060	3210	Shale & Lime
3210	3319	Lime & Shale
3319	3365	Lime & Shale
3365	3410	Lime & Shale DST #1
3410	3445	Lime
3445	3510	Lime
3510	3551	Lime DST # 2
3551	3640	Lime & Shale
3640	3700	Lime Conglomerate
3700	3722	Lime Log
3722		Total Depth D & A

RECEIVED  
STATE CORPORATION COMMISSION  
9-6-1967  
SEP 6 1967

CONSERVATION DIVISION  
Wichita, Kansas

We certify the above and foregoing to be true and correct copy of the log on the #1 Johnson "B" located in Ellis County, Kansas

Bill Laha President

Alma A. Miller Notary Public  
Subscribed and sworn to before me this 5th day of September, 1967, My commission expires May 31, 1970

