

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-23115-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 4 Twp. 12 Rge. 18 NE/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines
NE SW NE

Lease Owner Dreiling Ltd. of Colorado
Lease Name Hottman Well No. 1

Office Address 410 - 17th St., Suite 1140, Denver, Co. 80202
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole


Date Well completed 8-27 19 82
Application for plugging filed 9-7 19 82
Application for plugging approved 8-27 19 82
Plugging commenced 8-27-82 3:30 A.M. 19 82
Plugging completed 8-27-82 5:30 A.M. 19 82
Reason for abandonment of well or producing formation

Non-productive

If a producing well is abandoned, date of last production
None 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3700'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section 7 list

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	60' mud.	3603	3634	8-5/8	207'	None
Lansing	35' mud.	3464	3490			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Hole full of heavy mud. Cement plugs with 150 sacks of 50-50- pozmix with 6% gel, 4% cc. Cement pumped through drill pipe as follows:

- 1st cement plug at 775' with 80 sacks
- 2nd cement plug at 200' with 40 sacks
- 3rd wood and rubber 8-5/8 plug with solid hull bridge at 40' with 10 sacks
- 10 sacks in rathole
- No mousehole on the well

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hatliburton

STATE OF Colorado COUNTY OF Denver, ss.
Leslie Olson (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Olson

(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of September, 1982

Lorraine C. Murphy
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
9-9-1982
SEP 09 1982
CONSERVATION DIVISION
Wichita, Kansas

My commission expires 9-2-83