


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-051-20254-00-00
WELL PLUGGING RECORD

Ellis County. Sec. 4 Twp. 12 Rge. (E) 18 (W)

Location as "NE/CNW%SW%" or footage from lines SE SE SW
Lease Owner Allison & Black
Lease Name Johnson "D" Well No. 1
Office Address 1415 Wichita Plaza - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 5-15 1968
Application for plugging filed 5-15 1968
Application for plugging approved 5-15 1968
Plugging commenced 1:45 PM 5-15 1968
Plugging completed 3:00 PM 5-15 1968
Reason for abandonment of well or producing formation dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massy - Hays, Kansas
Producing formation none Depth to top _____ Bottom _____ Total Depth of Well 3686 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	0	0	204	8 5/8"	204	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole - ran 720' drill pipe & cemented with 75 sacks
180' with 25 sacks and 40' with 10 sacks & 2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & B DRILLING, INC.
Address 207 Petroleum Building - Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Bill Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar
207 Petroleum Building - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21th day of May, 19 68

May 31, 1970

Alma A. Neiser

Notary Public.

My commission expires _____

15-051-20254-00-00
B & B DRILLING, INC.

548 Petroleum Building
Wichita, Kansas 67202

May 21, 1968

DRILLERS LOG

Re: Johnson "D"
SE SE SW Sec. 4-12S-18W
Ellis County, Kansas

COMPANY: Allison & Black
CONTRACTOR: B & B Drilling, Inc.
TOTAL DEPTH: 3686'
COMMENCED: May 8, 1968
COMPLETED: May 15, 1968

0	204	Soil & Shale	
204	240	Shale	
240	1174	Shale & Sand	
1174	1388	Red Bed & Shale	
1388	1429	Anhydrite	
1429	1445	Shale	
1445	1865	Shale	
1865	2110	Shale	
2110	2390	Shale & Lime	
2390	2625	Shale & Lime	
2625	2815	Shale & Lime	
2815	3015	Shale & Lime	
3015	3165	Lime	
3165	3222	Shale & Lime	
3222	3325	Lime	
3325	3405	Lime	
3405	3475	Shale & Lime	
3475	3487	Lime	DST #1
3487	3560	Lime	
3560	3565	Shale & Lime	DST #2
3565	3640	Lime & Shale	
3640	3666	Lime	DST #3
3666	3676	Shale & Lime	
3676	3686	Arbuckle	
3686		Total Depth	D & A

RECEIVED
STATE CONSERVATION COMMISSION
MAY 22 1968
CONSERVATION DIVISION
Wichita, Kansas

We certify the above and foregoing to be true and correct copy of the log on the #1 Johnson "D", located in Ellis County, Kansas.

Bill Lahn President

Anna A. Nuis Notary Public

Subscribed and sworn to before me this
21th day of May, 1968
My commission expires May 31, 1970

