

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-00574-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec. 4 Twp. 12S Rge. 18W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Sierra Petroleum Co., Inc.

Lease Name SCHERMER Well No. 1

Office Address 420 W. Douglas Ave.

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 7/24/57 19

Application for plugging filed 7/23/57 19

Application for plugging approved 7/23/57 19

Plugging commenced 7/24/57 19

Plugging completed 7/24/57 19

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3650 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	203	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud from 3650 to 650'. Set wood plug at 650 with 20 sacks cement. Filled with mud from 650 to 195'. Set wood plug with 1/2 sack hulls and 15 sacks cement. Filled with mud to 40', with 1/2 sack hulls and 10 sacks cement to cellar 0.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.

Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

T. R. Sullivan (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.R. Sullivan

(Address)

SUBSCRIBED AND SWORN to before me this 26th day of July, 19 57

My commission expires 1-30-61



Margie Cooper
Notary Public.

PLUGGING
FILE SEC 4 T. 12 R. 18W
BOOK PAGE 31 LINE 16

RECEIVED
STATE CORPORATION COMMISSION
729-1957
JUL 29 1957
CONSERVATION DIVISION
Wichita, Kansas

15-051-00574-00-00

Sierra Petroleum Co., Inc.

SCHERMER #1

NE NE SW 4-12S-18W
Ellis County, Kansas

Total Depth: 3650*

Elev: 2060 KB

Comm: 7/13/57

Comp: 7/24/57

Casing:

Cement:

8 5/8 @ 203*

135 sks cement

FORMATION	DEPTH
Clay & sand	20
Post rock	30
Shale	203
Shale & shells	465
Sand	485
Shale	655
Sand	770
Sand, stone & shale	800
Shale	940
Sand	1000
Shale & Red Bed	1360
Anhydrite	1400
Red Bed & Shale	1600
Salt & shale	1810
Shale	1920
Shale & lime	3130
Lime	3611
Arbuckle	3650

Tops:	FORMATION	DEPTH
	Anhydrite	1360
	Heebner	3289
	Toronto	3309
	Lans. K. C.	3335
	Base K. C.	3552
	Conglomerate	3575
	Arbuckle	3616


STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

T.R. Sullivan

Subscribed and sworn to before me this 26th day of July, 1957.

Margie Cooper
 Notary Public



My commission expires: 1-30-61.

PLUGGING
 FILE SEC 4 T. 12 R. 18W
 BOOK PAGE 31 LINE 16

RECEIVED
 STATE CORPORATION COMMISSION
 7-29-1957
 JUL 29 1957
 CONSERVATION DIVISION
 Wichita, Kansas