

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-051-00156-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 4 Twp. 12 Rge. 18 (X) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Petroleum, Inc.
Lease Name Schermer 'B' Well No. 1
Office Address 305 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 2, 1953
Application for plugging filed October 2, 1953
Application for plugging approved October 2, 1953
Plugging commenced October 2, 1953
Plugging completed October 2, 1953
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3722 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	192'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 185' and wet wooden plug
at 185'. Placed 1/2 sack hulls ahead of
plug at 185'. Cemented and displaced
15 sacks cement through drill pipe onto
plug and hulls at 185'. Mudded up to
40' and set second wooden plug at 40'.
Placed 1/2 sack hulls on top of plug at
40'. Filled hole to bottom of well
cellar with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R.R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W.W. Fisher (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.W. Fisher

10-16-1953
CONSERVATION DIVISION
305 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 1953

My commission expires October 13, 1954

Charlotte Anderson
Notary Public.

24-7368-5 3-53-20M



PLUGGING
FILE SEC 4 T 12 R 18 W
BOOK PAGE 133 LINE 23

15-051-00156-00-00
DRILLER'S LOG SCHERMER 'B' #1

Petroleum, Inc., Operator

Section 4, Twp. 12S, Rge. 18W

Garvey Drilling Company, Contractor

Location: SE SE SE

Drilling Commenced: September 22, 1953

County: Ellis County, Kansas

Drilling Completed: October 1, 1953

Production: D & A

Casing Records: 8 5/8" @ 192' w/125 sax

R. T. D.: 3722'

Figures below indicate bottom of formation:

		<u>Top</u>
60	Rock Sand	
310	Shale & Shells	
890	Shale, Shells & Sand	Hebner: 3360(-1229)
1120	Sand	Toronto: 3384(-1253)
1116	Shale, Shells & Red Rock	Lansing: 3405(-1274)
1157	Anhydrite	Arbuckle: 3697(-1566)
2015	Shale, Salt & Shells	
3230	Line & Shale	
3722	Line	
3722	R.T.D.	

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W. W. Fish

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 8th day of October, 1953.

Charlotte Heidman
Notary Public

My commission expires: October 13, 1954

