


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-04558-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Ellis County. Sec. 5 Twp. 12S Rge. 18W (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines NE-NW-NW
Lease Owner Cooperative Refinery Association
Lease Name Kreutzer Well No. 1
Office Address Box 765 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 4, 1957 19
Application for plugging filed August 5, 1957 19
Application for plugging approved Verbal permission obtained 19
Plugging commenced August 4, 1957 19
Plugging completed August 4, 1957 19
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3565 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	253'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged at 12:00 noon August 4, 1957. Filled hole with rotary mud from 3565' to 600'. Set first plug at 600'. Cemented with 20 sks cement. Filled up to 240' with mud. Set second plug at 240' and cemented with 15 sks cement. Filled hole up to 40' with mud and set top plug. Cemented with 10 sks cement.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Cooperative Refinery Association
Address Box 765 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
John H. Nation (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Nation
Box 765 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of August, 1957

My commission expires Sept. 24, 1960



PLUGGING
FILE SEC. 5 T. 12 R. 18W
BOOK PAGE 34 LINE 18

RECEIVED
STATE CORPORATION COMMISSION
8-6-1957
AUG 6 1957
CONSERVATION DIVISION
Wichita, Kansas

15-051-04558-00-00

DRILLERS LOG

Kreutzer #1
Loc: NE-NW-NW
Sec: 5-12S-18W
Ellis County, Kansas
Operator: Cooperative Refinery Ass'n
Contractor: Cooperative Refinery Ass'n
-----Rig-#5-----

Elevation: 2052 R.B.
Csg: 8-5/8" @ 253' w/150 sk. posmix 2% cc
Comm: 7-23-57 Comp: 8-4-57
Total Depth: 3565'

<u>From</u>	<u>To</u>	<u>Formation</u>
0	252	Clay, postrock, shale
252	260	Cement
260	1065	Shale & sand
1065	1350	Shale & sand
1350	1368	Shale
1368	1410	Anhydrite
1410	1600	Shale & shells
1600	1920	Shale & shells
1920	2025	Shale, lime
2025	2195	Shale & lime
2195	2305	Lime & shale
2305	2335	Lime & shells
2335	2354	Lime & shells
2354	2385	Shale
2385	2520	Lime & shale
2520	2645	Lime & shell
2645	2730	Shale, lime, shells
2730	2840	Lime & shale
2840	2980	Lime & shale
2980	3080	Shale, sand
3080	3130	Lime & shale
3130	3180	Lime & shale
3180	3240	Shale & Lime
3240	3285	Lime & shale
3285	3320	Lime & shale
3320	3365	Lime & shale
3365	3410	Lime
3410	3455	Lime
3455	3475	Lime & shale
3475	3515	Lime & shale
3515	3550	Lime
3550	3565	Lime & shale
		R.T.D.

(STATE OF KANSAS)

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Kreutzer #1 well, located NE-NW-NW of Section 5-12S-18W, Ellis County, Kansas.

Subscribed and sworn to before me this 16 day of August 1957.

My commission expires: August 17, 1957

John H. Nation
Donald E. Hunt

RECEIVED
STATE CORPORATE COMMISSION

8-20-1957
AUG 20 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 5 T. 12 R. 18W
BOOK PAGE 34 LINE 18