

15-051-19137-00-00
WELL PLUGGING RECORD

OR FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Ellis County. Sec. 6 Twp. 12 Rge. 18 (E) 18 (W)
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE $\frac{1}{4}$ NE $\frac{1}{4}$ NW $\frac{1}{4}$
 Lease Owner. Petroleum, Inc.
 Lease Name. Harman Well No. 1
 Office Address. 314 Derby Bldg., Wichita, Kans.
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 12-24-48 19
 Application for plugging filed 12-24-48 19
 Application for plugging approved 19
 Plugging commenced 12-24-48 19
 Plugging completed 12-24-48 19
 Reason for abandonment of well or producing formation.

If a producing well is abandoned, date of last production.....19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....YES.....

Name of Conservation Agent who supervised plugging of this well.....Eldon R. Petty.....

Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet.....

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled hole with heavy mud; set bottom plug at 200'; cemented with 15 sack cement; filled with heavy mud on top; set wood plug @ 30'; cemented with 10 sack cement

12-30-1948

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... Petroleum, Inc.
Address..... 314 Derby Bldg., Wichita, Kans.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Charles M. Searle (employee of owner) or (~~owner or operator~~) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles H. Seale

.....
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December 19 48

My commission expires October 27, 1952

Marjorie Bradshaw
Notary

Notary Public.

22-2625

2-48-15M

2-48-15M
PLUGGING
FILE SEC 6 T 18 R 186
BOOK PAGE 76 LINE 38

15-051-19137-00-00

WELL LOG

Petroleum, Inc.
Harman #1

Sec. 6; T 12; R 18W
NE/4 NE/4 NW/4
County: Ellis

Total Depth: 3755'
Comm: 12-9-48 Comp: 12-24-48
Contractor: J.D. Ferrell Drilling Co., Inc.
Issued: 12-27-48 Rotary O-3755'

Elevation 2125 D.F.
Production: Dry

Casing: 8 5/8" 357' cemented with 200 sax
bulk cement; 2 Sax C.C.
Cement circulated.

Figures indicate bottoms of Formations:

cellar	8
sand & surface soil	125
shale	191
sandy shale & shells	357
sticky shale	425
shale & shells	675
sandy shale & shells	930
sand	1195
shale & shells	1455
Anhydrite	1505
shale & shells	2010
lime & shale	2450
lime	2495
lime & shale	2520
lime (rock)	2543
shale & lime	2580
lime & shale	2840
shale	2900
shale & lime	2925
shale	2943
gyp & shale	2965
shale & shells	2990
shale & lime	3050
shale	3080
lime & shale	3284
lime	3325
lime & shale	3352
lime	3370
lime & shale	3454
lime	3707
conglomerate	3725
Arbuckle	3755
Total Depth	3755

Tops:	Topeka	3189
	Kans. City	3417
	Arbuckle	3725

12-30-1948

We hereby certify this to be a correct and accurate log of
the above described well as shown on the daily drilling Reports.

J.D. FERRELL DRILLING CO., INC.,

BY:

J.W. Rallsback
J.W. Rallsback

Subscribed and sworn to before me this 27th day of December, 1948

My commission expires:
Oct., 15, 1951

Merle Y. Saunders
Notary Public (Parton Co.)

