

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-00347-00-00
WELL PLUGGING RECORD

Ellis County, Sec. 6 Twp. 12S Rge. (X) 18(W)

Location as "NE/CNW/SW" or footage from lines SW SW SE

Lease Owner Peel-Hardman Oil Operators

Lease Name Leiker Well No. 1

Office Address R. R. #3, Box 144B, Wichita 15, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 2-15 1959

Application for plugging filed 2-16 1959

Application for plugging approved 2-16 1959

Plugging commenced 2-16 1959

Plugging completed 2-16 1959

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3780 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	200'	8 5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

From 3780' to 661 1/2' - Heavy Rotary Mud
 " 661 1/2' to 660' - Wooden Plug
 " 660' to 595' - 20 sacks cement
 " 595' to 181 1/2' - Heavy Rotary Mud
 " 181 1/2' to 180' - Wooden Plug
 " 180' to 118' - 20 sacks cement
 " 118' to 41 1/2' - Heavy Rotary Mud
 " 41 1/2' to 40' - Wooden Plug
 " 40' to 6' - 10 sacks cement
 " 6' to surface - Cellar

RECEIVED
STATE CORPORATION COMMISSION
2-26-1959
FEB 26 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.

William Herbert (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *William Herbert*

R. R. #3, Box 144B, Wichita 15, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of February, 1959

My commission expires March 4, 1962

Notary Public.

PLUGGING
FILE SEC 6 T 12 R 18W
BOOK PAGE 20 LINE 24

15-051-00347-00-00

DRILLER'S LOG

Company: Peel-Hardman Oil Operators

Location: SW SW SE
Sec. 6, Twp. 12S, Rge. 18W

Farm: Leiker Well No. 1

County: Ellis,
Kansas

Total Depth: 3780'

Comm.: 2-6-59 Comp.: 2-16-59

Elevation:

Contractor: Glenn W. Peel Drilling Co.

Production: Dry

Casing: 8 5/8" @ 200' Cem.

Figures below indicate bottom of formations

Sand and shale	0	200'
Shale		555
Shale and sand		1275
Anhydrite		1535
Shale		1585
Shale and shells		2110
Shale and lime		3060
Lime		3780
Total Depth		3780

This is to certify that the above information is to the best of my knowledge true and correct.

GLENN W. PEEL DRILLING COMPANY

BY: *Glenn W. Peel*

SUBSCRIBED AND SWORN TO before me this 25th day of February, 1959.

My commission expires March 4, 1962.

Marion M. Herbert
Notary Public

STATE COR. 2-26-1959

CONSERVATION DIVISION

PLUGGING	
FILE	SEC. 6 T. 12 R. 18W
BOOK	PAGE 20 LINE 24