


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

15-051-20045-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 6 Twp. 12S Rge. (E) 18(W)  
Location as "NE/CNW&SW" or footage from lines. NE SE SW  
Lease Owner J. A. Allison & Thomas E. Black  
Lease Name McINTOSH Well No. 1  
Office Address 1415 Wichita Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 16, 1967  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced April 16, 1967  
Plugging completed April 16, 1967  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Leo Massey)

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3514 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	207'	8-5/8"	4/11/67	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 550 Feet;  
Plug and 25 sacks of Cement thru the  
Drill Pipe; Mud to 200 Feet; Plug and  
20 sacks Cement thru the Drill Pipe;  
Mud to 40 Feet; 1/2 sack Halls, Plug  
bridged with Kelly and 8 sacks Cement  
to Base of Cellar; 2 sacks Cement in  
Rat Hole. Job completed at 11:30 A.M.

RECEIVED  
STATE CORPORATION COMMISSION  
4-18-1967  
APR 18 1967  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co.  
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Lawrence F. Gray of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray  
500 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of April, 1967

November 26, 1970.

Louise K. Whitted  
(Notary Public)



15-051-20045-00-00

DRILLERS LOG

McINTOSH NO. 1

CASING RECORD: 8-5/8" @ 207'  
w/135 sax cement

TOTAL DEPTH: 3514'

COMPANY: J. A. Allison & Thomas E. Black

CONTRACTOR: Sage Drilling Co., Inc.

COMMENCED: April 11, 1967

COMPLETED: April 16, 1967

DESCRIPTION: NE SE SW  
Sec. 6-12S-18W  
Ellis County, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock	0	40	
Yellow Shale	40	150	
Shale	150	750	
Sand & Shale	750	950	
Sand	950	1188	
Shale	1188	1255	
Shale & Shells	1255	1516	
Anhydrite	1516	1551	
Shale & Shells	1551	1675	
Shale, Shells & Lime	1675	2170	
Lime & Shale	2170	3280	
Lime	3280	3445	
Lime & Shale	3445	3514	

**RECEIVED**  
STATE CORPORATION COMMISSION  
4-18-1967  
APR 18 1967  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray  
Lawrence F. Gray

Subscribed and sworn to before me this 17th day of April, 1967.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1970.