

Locate well correctly on above Section Plat

Ellis County, Sec. 7 Twp. 12 Rge. 18 (E) (W) X
 Location as "NE/CNW/SW" or footage from lines C/NW/NE
 Lease Owner Woodman-Iannitti Drilling Company
 Lease Name Johnson Well No. 1
 Office Address Box 308, Great Bend, Kansas 67530
 Character of Well (completed as Oil, Gas or Dry Hole)
 Date well completed 19__
 Application for plugging filed April 16 19 76
 Application for plugging approved 19__
 Plugging commenced April 22 19 76
 Plugging completed May 4 19 76
 Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19__
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3785 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	201'	none
				5 1/2"	3746'	1,051.15'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 3400'. Dumped 20 gals. sand and 5 sacks cement.

Pulled a total of 33 joints of 5 1/2" casing. (parted)

Plugged well with 3 sacks hulls, 20 sacks gel and 120 sacks

50/50 Pozmix with 6% added gel.

RECEIVED
 STATE CORPORATION COMMISSION
 5-7-1976
 MAY 07 1976

CONSERVATION DIVISION
 WICHITA, KANSAS

Name of Plugging Contractor Rockhold Engineering, Inc.
 Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.
 James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 Box 698, Great Bend, Kansas 67530 (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of May 1976

My commission expires 1980
 KAREN M. MORTON
 Barton County, Kansas
 Notary Public

Karen M. Morton
 Notary Public

15-051-30052-00-00

KANSAS GEOLOGICAL SOCIETY

KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU

KANSAS GEOLOGICAL SOCIETY BUILDING

508 EAST MURDOCK - WICHITA, KANSAS

ORIGINAL

STENCILED

MAR 11 1967

COMPANY Woodman & Iannitti Drilling Co.

SEC. 7 T. 12 R. 18W


FARM Johnson NO. 1

LOC. C NW NE

TOTAL DEPTH 3752

COUNTY Ellis

COMM. November 25, 1966 COMP. December 4, 1966



SHOT OR TREATED

CONTRACTOR Woodman & Iannitti Drilling Co.

ISSUED 3-11-67

CASING

20	10	
15	8 5/8 @ 191'	
12	6	w/135 SX
13	5" @ 3746'	w/75 SX

ELEVATION 2183 K.B.

PRODUCTION PMP 20 BOPD & 30 WTR. (ARB 3746-54)

FIGURES INDICATE BOTTOM OF FORMATIONS

170	Post Rock & Clay
200	Blue Shale
695	Shale
975	Shale
1170	Sand
1380	Red Bed
1494	Red Bed
1534	Anhy
1635	Shale & Shells
2070	Shale & Shells
2195	Lime
2380	Lime
2490	Lime
2595	Lime
2755	Lime
2830	Lime
3010	Lime
3135	Lime
3232	Lime
3300	Lime
3355	Lime
3410	Lime
3435	Lime
3520	Lime
3530	Lime
3583	Lime
3640	Lime
3650	Lime
3695	Lime
3752	Lime

TOPS: SCOUT

Anhydrite	1494
Heebner	3422
Toronto	3442
Lansing	3466
Arbuckle	3741

I certify the above to be a true and correct copy of the driller's log and the geological tops to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman

RECEIVED
STATE CORPORATION COMMISSION
4-19-1976
APR 19 1976
CONSERVATION DIVISION
Wichita, Kansas

APR 1 1976