


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-21075-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 7 Twp. 12 Rge. 18 ~~EW~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE SW



Locate well correctly on above
Section Plot

Lease Owner Raymond Oil, Co., Inc.
Lease Name Stackhouse Well No. 1
Office Address 200 W. Douglas, Suite 800 Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed April 23 1979
Application for plugging filed April 23 1979
Application for plugging approved April 23 1979
Plugging commenced April 23 1979
Plugging completed April 23 1979
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3740'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 720' w/70 sacks 50/50 Pozmix 4% gel thru d p.
Middle Plug @ 210' w/35 sacks
Top Plug @ 40' w/1/2 sacks hulls and 10 sacks cement
2 sacks cement rathole

RECEIVED
STATE CORPORATION COMMISSION
4-26-1979
APR 26 1979

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.


STATE OF KANSAS COUNTY OF BARTON, ss.
Bill Draney (employee of owner) or (owner/operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
P.O. Box 823 - Great Bend, Ks 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of April, 1979

Dorothy M. Hague
Notary Public.



15-051-21675-00-00

DRILLERS' WELL LOG

DATE COMMENCED: April 16, 1979
DATE COMPLETED: April 23, 1979

Raymond Oil Co., Inc.
STACKHOUSE # 1
SW NE SW
Sec 7, T12S, R18 W
Ellis County, Ks.

0 - 50	Clay, Sand, Post Rock
50 - 100	Post Rock
100 - 975	Shale
975 - 1190	Sand
1190 - 1508	Shale
1508 - 1553	Anhydrite
1553 - 3215	Shale & Lime
3215 - 3443	Lime
3443 - 3447	Shale
3447 - 3487	Lime & Shale
3487 - 3734	Lime
3734 - 3740	Lime & Shale
3740	RTD

ELEVATION: 2195 K B

FORMATION DATA	
Anhydrite	1508
Topeka	3215
Heebner	3443
Toronto	3469
Lansing-KC	3487
Base KC	3734
RTD	3740

SURFACE PIPE: Set
used 10 3/4" pipe
O 217' w/135 sacks
common, 2 1/2 gal,
3 1/2 cc.

A F F I D A V I T

State of Kansas
County of Barton) ss.

Bill Draney, of lawful age does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 24 day of April, 1979

Clarity M. Haque
Notary Public

My Comm. Expires: April 11, 1982



RECEIVED
CONSERVATION COMMISSION
4-26-1979
APR 26 1979
CONSERVATION DIVISION
Wichita, Kansas