

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-00651-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Ellis County. Sec. 9 Twp. 12 Rge. (E) 18 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW/4 NW/4 NE/4

Lease Owner Aylward Drilling Company

Lease Name Holy Cross Well No. 1

Office Address 813 First Nat'l. Bank Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed December 2, 1951

Application for plugging filed December 7, 1951

Application for plugging approved December 10, 1951

Plugging commenced December 17, 1951

Plugging completed December 20, 1951

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well E. Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3691 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	125	none
				5-1/2	3682	3129'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rock from 3691' to 3670' and cemented with 4 sax cement. Set bridge at 160', dumped 15 sax of cement on fresh water bridge, mudded hole to 40' and set bridge and filled hole with 10 sax cement.

RECEIVED
1-5-1952
JAN - 5 1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Aylward Drilling Company

Address 813 First National Bank Bldg.
Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Lewis Stoy (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lewis Stoy

1923 Monroe Street, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of January 1952.

My commission expires _____
Alfred F. Skalsky
Notary Public
My commission expires July 9, 1952

22-5138-s 9-48-10M
PLUGGING
FILE SEC 91-12R-180
BOOK 129 LINE 52

Alfred F. Skalsky
Notary Public

15-051-00651-00-00

HOLY CROSS #1

Casing Record:

8-5/8" - 125'
5-1/2" - 3682'

Company: Aylward Drilling Company Et Al
Contractor: Aylward Drilling Company
Commenced: November 19, 1951
Completed: December 2, 1951

Description:
NW NW NE
Sec. 9-12S-18W
Ellis County, Kansas
Elev: 2121'
Pot. D. & A.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay & Shale	0	43	
Post rock & lime	43	86	
Shale blue	86	125	Set 8-5/8" casing at 125'
Shale & Shells	125	485	and cemented with 90 sax.
Shale	485	615	
Red bed and sand	615	650	
Shale Grey	650	715	
Sand & Shale	715	840	
Shale	840	900	
Sand	900	1070	
Shale & Sand	1070	1200	
Shale Shells	1200	1385	
Anhydrite	1385	1421	
Shale	1421	1536	
Shale Shells & Lime	1536	1855	
Shale & Lime	1855	2300	
Lime	2300	2345	
Lime Shale	2345	2454	
Lime	2454	2870	
Shale	2870	2880	
Lime	2880	2990	
Lime & Shale	2990	3090	
Lime	3090	3150	
Lime Shale	3150	3237	
Lime	3237	3691	Set 5-1/2" casing at 3682'
			and cemented with 100 sax.

TOPS:

Heebner 3346' -1225'
Lansing 3388' -1267'
Arbuckle 3681' -1560'

1-5-1952

- #1 DST: 3301-3315', open 1 hr. recovered 30' drilling fluid, no oil, 15 min. shut in BHP. 940#.
- #2 DST: 3472-3496', open 1 hr. recovered 285' salt water, no shows, 15 min. shut in BHP. 1000#.
- #3 DST: 3676-3691', open 1 hr. recovered 10' clean oil, 25' slightly oil cut mud, 15 min. shut in BHP. 600#.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

[Signature]
Al Skalsky

Subscribed and sworn to before me this 4 day of January, 1952.

PLUGGING

[Signature]
Notary Public

My commission expires: July 16, 1952