

Locate well correctly on above Section Plat

Ellis County, Sec. 9 Twp. 12 Rge. 18 (E) W (W)
 Location as "NE/CNW&SW" or footage from lines SW NW NE
 Lease Owner F & M Oil Co.
 Lease Name SCHMEIDLER Well No. 1
 Office Address 603 Union Center Building, Wichita, Kansas 67202
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed September 22 1975
 Application for plugging filed September 22 1975
 Application for plugging approved September 22 1975
 Plugging commenced September 22 1975
 Plugging completed September 22 1975
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3720 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Hole full of heavy mud.
 Set plug @ 600' w/70 sacks 50/50 Pozmix, 2% Gel.
 Come up hole to 185' set plug w/20 sacks 50/50 Pozmix, 2% Gel.
 Top plug set @ 40' w/1/2 sack hulls and 10 sacks cement

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Duke Drilling Co.
 Address Box 823, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON
 Wayne Dobbs (employee of owner) or (XXXXXXXXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne Dobbs
 P. O. Box 823, Great Bend, Kansas (Address)

Subscribed and sworn to before me this 22nd day of September 1975
 My commission expires April 11, 1978



Dorothy M. Hague
 Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION
 9-24-1975
 SEP 24 1975

DRILLERS' WELL LOG

DATE COMMENCED: September 15, 1975
 DATE COMPLETED: September 22, 1975

F & M Oil Co.
 SCHEIDLER # 1
 SW NW NE of Sec 9-T12-R18W
 Ellis County, Kansas

ELEVATION: 2147' K.B.

0 - 60'	Post Rock and Clay
60 - 1160'	Shale, Shells and Sand Streaks
1160 - 1436'	Red Bed
1436 - 1480'	Anhydrite
1480 - 1995'	Shale and Shells
1995 - 3382'	Lime and Shale
3382 - 3386'	Shale
3386 - 3425'	Lime and Shale
3425 - 3688'	Lime
3688 - 3720'	Lime, Chert, Chale
3720'	RTD

FORMATION TOPS

Anhydrite	1436'
Heebner	3382'
Lansing	3425'
Conglomerate	3688'
RTD	3720'

SURFACE PIPE:

Set 206' of 8 5/8", 28# used
 pipe w/125 sacks Common, 2% Gal,
 3% cc.

A F F I D A V I T

STATE OF KANSAS }
 COUNTY OF BARTON } ss.

Wayne Dobbs, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 23rd day of September, 1975.

Lois M. Hague
 Notary Public



9-24-1975