

15-051-22254-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 10 TWP. 12S RGE. 18W E/W
Location as in quarters or footage from lines:
SW/NE/NE

Lease Owner Parrish Corp.
Lease Name Baker "A" Well No. 1
Office Address 110 N. Market - Suite 201, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed March 22, 1981
Application for plugging filed Verbal application
Plugging commenced March 22, 1981
Plugging completed March 22, 1981
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation _____ Depth to top _____ bottom T.D. 3723'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	216'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3723' (rotary total depth) to 780 ft. Set plug at 780 ft. and cemented with 65 sacks cement.

Filled hole with heavy rotary mud from 780 ft. to 210 ft. Set plug at 210 ft. and cemented with 30 sacks cement. Filled hole with heavy rotary mud from 210 ft. to 40 ft. Set solid plug at 40 ft and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Younger, Agent (~~employee of owner~~) ~~xxx (owner xxx operator) xxx~~
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary Younger
251 N. Water - Suite 10
Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of April, 1981

My Commission expires: July 25, 1982

Elsie Willison
Elsie Willison - Notary Public.



RECEIVED
STATE CORPORATION COMMISSION
APR 10 1981
4-10-1981
CONSERVATION DIVISION
Wichita, Kansas

15-051-22254-00-00
KANSAS DRILLERS LOG

COMPANY Parrish Corp.

SEC. 10 T. 12S R. 18W

FARM Baker "A" NO. 1

LOC. SW/NE/NE 33

COUNTY Ellis

ROTARY TOTAL DEPTH 3723'
 COMM. March 12, 1981 COMP. March 22, 1981
 CONTRACTOR H-30, INC. (Rig #2)
 ISSUED April 8, 1981

CASING

10 3/4"
 8 5/8" Set at 216' cemented with 150 sxs cement
 5 1/2"
 4 1/2"


ELEVATION 2,157' G.L.

FIGURES INDICATE BOTTOM OF FORMATIONS

Post Rock, Sand and Shale	80'
Shale	220'
Sand and Shale	1,443'
Shale	1,975'
Shale and Lime	2,135'
Lime and Shale	2,530'
Shale	2,720'
Lime and Shale	3,320'
Lime	3,480'
Lime and Shale	3,545'
Lime	3,723'
Rotary Total Depth	3,723'


I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.


 Gary Younger

State of Kansas)
) ss:
 County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county, and state this 8th day of April, 1981.


 Elsie Willison - Notary Public

My Commission Expires:
 July 25, 1982



RECEIVED
 STATE CORPORATION COMMISSION
 4-10-1981
 APR 10 1981
 CONSERVATION DIVISION
 Wichita, Kansas